

LSU Stadium Mount Proposal

Overview:

Design is to be mounted to the side of the concrete foundation. It will extend 5 feet over the top of the foundation and 6 feet away from the foundation. It will be hinged at the base allowing to tilt the camera over the top railing of the stadium for servicing. There will be a tension rod connected to the side of the foundation to both support the structure and allow the structure to be leaned in over the railing.

