

SECTION 02 41 19
SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Salvage of existing items to be reused or recycled.

1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Detach items from existing construction and deliver them to User ready for reuse.
- C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.
- D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

- A. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, antiques, and other items of interest or value to Owner that may be encountered during selective demolition remain Owner's property. Carefully remove and salvage each item or object in a manner to prevent damage and deliver promptly to User.

1.5 SUBMITTALS

- A. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure User's on-site operations are uninterrupted.
2. Interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.
4. Coordination of User's continuing occupancy of portions of existing building and of User's partial occupancy of completed Work.
5. Means of protection for items to remain and items in path of waste removal from building.
6. Method of providing on-site security.

B. Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged.

C. Predemolition Photographs or Videotapes: Show existing conditions of adjoining construction and site improvements, including finish surfaces that might be misconstrued as damage caused by selective demolition operations.

1.6 QUALITY ASSURANCE

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ANSI A10.6 and NFPA 241.

1.7 PROJECT CONDITIONS

A. User will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so that User's operations will not be disrupted.

1. Comply with requirements specified in Section 01 10 00 "Summary of Work."

B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

C. Notify Architect in writing of discrepancies between existing conditions and Drawings before proceeding with selective demolition.

D. Hazardous Materials:

1. Upon encountering any previously unidentified materials which he suspects may contain asbestos, the Contractor shall immediately cease all work in the immediate vicinity of the suspected materials and notify the Designer and the Owner. The Owner shall retain consultants to identify the suspected materials. Upon identification, the Owner reserves the right to contract separately for the removal or require the Contractor (if qualified) to remove

said materials in accordance with the following provision. In any case, the work shall be performed by a licensed and certified Abatement Contractor.

2. The Louisiana Department of Environmental Quality (D.E.Q.) has issued the Louisiana Emission Standards for Hazardous Air Pollutants. Where asbestos is encountered in a project, the Contractor shall comply with all laws and ordinances pertaining to asbestos handling and abatement, including the latest revision of LAC 33:III, Chapter 25, Subchapter F, Emission Standards for Hazardous Air Pollutants, LAC 33: III, Chapter 27, Asbestos Containing Materials in Schools and Public Buildings and LAC:33III, Chapter 51, Subchapter M, Section 5151, Emission Standards for Asbestos.

Notification should be addressed to:

Asbestos Supervisor
Louisiana Department of Environmental
Quality
Air Quality Division
Post Office Box 4313
Baton Rouge, Louisiana 70831-4313

3. If the Owner chooses to remove any previously unidentified materials by utilizing different Contractors, the Contractor shall cooperate fully with the Owner's consultants and asbestos abatement Contractor permitting them full access to the project, and shall not resume work in the vicinity of the suspected materials until advised by the Designer and the Owner that it is safe to do so.

4. The Designer shall specify the use of third party air monitoring firms (with no ownership associations with the contractor) in an expanded inspection role as follows: document daily work activities, number of workers present, track and quantify removal quantities (where necessary and where unit pricing is called for in specifications), perform pre-clearance inspection and verify on a daily basis the contractor work with the design documents and report to the designer any conflicts.

5. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify both Architect and Owner in writing.

E. Storage or sale of removed items or materials on-site is not permitted.

F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

1. Maintain fire-protection facilities and life safety components in service during selective demolition operations.

1.8 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- B. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- C. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Owner and Architect.
- D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs or preconstruction videotapes.
 - 1. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.
- E. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.
- F. All existing insulation above affected ceilings is to be removed and stored prior to demolition.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems: Maintain services/systems indicated to remain and protect them against damage during selective demolition operations.
 - 1. Comply with requirements for existing services/systems interruptions specified in Section 01 10 00 "Summary of Work."

- B. Service/System Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
 - 1. Arrange to shut off indicated utilities with utility companies.
 - 2. If services/systems are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
 - 3. Cut off pipe or conduit to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing.

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Comply with requirements for access and protection specified in Section 01 50 00 "Temporary Facilities and Controls."
- B. Temporary Facilities: Provide temporary barricades and other protection by Authority Having Jurisdiction required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
 - 2. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
 - 3. Cover equipment or any other items that have not been removed.
 - 4. Comply with requirements for temporary enclosures, run-off control specified in Section 01 50 00 "Temporary Facilities and Controls."
- C. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 - 1. Strengthen or add new supports when required during progress of selective demolition.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. Removed and Salvaged Items:
 - 1. Clean salvaged items.
 - 2. Store items in a secure area until delivery to Owner. Verify location with Owner.
- B. Removed and Reinstalled Items:
 - 1. Clean and repair items to functional condition adequate for intended reuse. Paint equipment to match new equipment.
 - 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
 - 3. Protect items from damage during transport and storage.
 - 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- C. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete. Coordinate location with User.

3.5 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

- A. Concrete: Demolish in sections. Cut concrete full depth at junctures with construction to remain and at regular intervals, using power-driven saw, then remove concrete between saw cuts.
- B. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, then break up and remove.

3.6 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 3. Remove all debris from work site daily to Staging Area.
- B. Burning: Do not burn demolished materials.

- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

3.7 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 02 41 19