



NOTE:

- FOR DRAIN PIPES REQUIRED ALONG THE FRONT, THESE SPECIFICATIONS INCLUDE THE BELL AND SPIGOT TYPE WITH:
 - 1" RING RUBBER GASKETS, THE EQUIVALENT ARCH SIZES ARE REQUIRED WHEN ADEQUATE ROUND PIPE CAN NOT BE ACHIEVED WITH ROUND PIPE.
 - THE BELLS OF THE PIPES SHALL BE LAID UPSTREAM.
 - ALL JOINTS SHALL BE WRAPPED WITH GEOTEXTILE FABRIC.
 - ALL TRENCHES REQUIRE A 3" COMPACTED SAND OR LIMESTONE DUNE.
- SEE SHEET C-5 FOR FIRE HYDRANT & PIPE BEDDING DETAILS.
- ALL PUMP AND CONDUIT SYSTEMS ARE DIAGRAMMATICALLY DRAWN. CONTRACTOR/OWNER TO VERIFY COMPONENT, THE-SIZES AND ELECTRICAL CONDITIONS PRIOR TO START OF CONSTRUCTION.
- CONTRACTOR/OWNER TO PROVIDE EXTENSION TO ADJUST ELEVATION OF LIFT STATION AS REQUIRED. FIELD VERIFY.
- INSTALL NEW 6" MECHANICAL WALL SERVICES IN LIFT STATION.
- ALL SEWER LINE INVERT ELEVATIONS ARE ±.

LEGEND

- 8" W. --- EXISTING 8" WATER LINE
- 4" W. --- EXISTING 4" SEWER LINE
- W --- NEW 2" WATER LINE
- S --- NEW 4" & 8" SEWER LINE
- DR --- NEW 4" DRAIN LINE
- 6" FW --- NEW 6" FIRE WATER LINE
- 5" C ELECT --- NEW 5" C ELECT. CONDUITS
- GAS --- GAS
- NEW FIRE HYDRANT
- BOLLARDS
- NEW FIRE HYDRANT

UTILITIES PLAN

SCALE: 1"=30'-0"



<p>SLIDELL WEST SHOPPING CENTER</p> <p>DAMMON ENGINEERING, INC.</p> <p>1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458 DAMMONENGINEERING.COM</p>	<p>UTILITIES PLAN</p> <p>GARY MUTTER 2170 HWY 190 WEST SLIDELL, LOUISIANA</p>	<p>JOB NO. 1700</p> <p>DATE: 10-25-05</p> <p>SHEET 5</p> <p>C-4</p> <p>OF 24</p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------