

**STATE OF LOUISIANA**  
Department of Public Safety and Corrections  
Office of State Fire Marshal Code Enforcement and Building Safety  
8181 Independence Boulevard  
Baton Rouge, Louisiana 70806  
225-925-4920

HENRY H. FRY  
DEPUTY ASSISTANT SECRETARY

**NEW CONSTRUCTION**

ROBERT SOLLBERGER  
ROBERT SOLLBERGER, ARCHITECT  
150 CHAMALE DR  
SLIDELL, LA 70460-0000

RE: P0300916  
SOUTHSIDE CAFE  
3154 PONCHARTRAIN DR  
SLIDELL, LA 70458-0000

NFPA 101, 2003

ASSEMBLY 300 OCCUPANTS OR LESS

Dear Applicant:

This is to advise that we have reviewed the drawings and specifications for the subject proposed construction and have determined that they appear to satisfactorily comply with the adopted laws, codes, rules and regulations of The State Fire Marshal subject to the following requirements:

1. **LRS 40:1728 The State Uniform Construction Code is enforced as promulgated by local political subdivisions of the state. Contact the local building official of the applicable local political subdivision to coordinate compliance with State Uniform Construction Code requirements.**

NOTE: THE COMMENTS LISTED BELOW IDENTIFY APPARENT DEFICIENCIES DETECTED IN OUR REVIEW OF THE DOCUMENTS SUBMITTED.

2. **101:7.2.1.3 Provide landings outside exterior doors level with the interior finish floor.**
3. **101:7.2.2.4.1 Stairs and ramps shall have handrails on both sides and shall be provided within 30 inches of all portions of the required egress width of stair.**
4. **LRS 40:1651 Submit chemical fire suppression system shop drawings with plan review application and fee prior to installation of any work of this section. Such work shall not commence until shop drawings have been found to be in compliance with applicable codes by this office. Submittal shall include a copy of this letter and shall be in accordance with the rules for such by this office. (Systems include hoods, halon, wet or dry chemical systems, etc.)**
5. **NOTE: HOOD CONSTRUCTION IS NOT AUTHORIZED until a satisfactory review by this office is performed for determining compliance with minimum code requirements. Compliance with NFPA 96, regarding cooking hood construction/installation, cannot be determined with the documents received. (A copy of the "Kitchen Exhaust Hood/Duct/Suppression System Requirements" is enclosed for your use). The following specific information was not apparently provided:**

Nov 8, 2005  
P0300916 - PAGE 1