



ADDENDUM NUMBER FOUR (4)

DATE: AUGUST 6, 2009

PROJECT: JOSEPH B. LANCASTER ELEMENTARY SCHOOL
ST. TAMMANY PARISH SCHOOL BOARD

OWNER: ST. TAMMANY PARISH SCHOOL BOARD
321 THEARD STREET
COVINGTON, LOUISIANA

GGB PROJECT NO.: 0825
STPSB PROJECT NO.: 0825

ARCHITECT: GASAWAY-GASAWAY-BANKSTON
A PROFESSIONAL ARCHITECTURAL CORPORATION
P. O. BOX 2156
HAMMOND, LA 70404

THE FOLLOWING ADDITIONS, CLARIFICATIONS, DELETIONS, AND/OR CORRECTIONS TO THE ORIGINAL CONTRACT DOCUMENTS ARE HEREBY SPECIFICALLY MADE A PART OF THOSE ORIGINAL CONTRACT DOCUMENTS WITH THE SAME FORCE AND EFFECT AS THOUGH ORIGINALLY SET FORTH IN FULL. CHANGES IN SPECIFICATIONS SHALL BE LISTED AND OTHERWISE EXPLAINED BY THIS ADDENDUM NO. FOUR (4). ANY CONTRADICTIONS IN THESE DOCUMENTS SHALL BE IMMEDIATELY POINTED OUT TO THE ARCHITECT SO THAT A DECISION CAN BE RENDERED.

GENERAL

1. Refer to Addendum No. 3, Item No. 3 and 11:
Clarification: Addendum No. 3 contains the addition of two (2) allowances for additional excavation and backfill work. Both allowances are to be included in the Base Bid and Add Alternate No. 1. The General Contractor will be required to list each allowance individually on their Schedule of Values.

CIVIL - PLANS

2. Refer to Sheet C104:
A 3" PVC irrigation sleeve is to be added just east of the eastern most drive leading to the parent/student (car) drop off area. The sleeve is to extend from north to south under the entrance drive to allow irrigation of the areas south of the entrance drive.
3. Refer to Sheet C104 for locations of irrigation sleeves.

ARCHITECTURAL - SPECIFICATIONS

4. Refer to Section 02810 - Automatic Landscape Irrigation System, Paragraph 1.1(B) shall read as follows:
"The irrigation system installer and supplier shall design the system as required to meet the requirements of this specification and as required to provide the necessary water of all trees, shrubs and surrounding sodded areas."
5. Refer to Section 02810 - Automatic Landscape Irrigation System, clarification:
No irrigation system shall be provided in hydroseeded areas.
6. Refer to Addendum No. 2, Item No. 38:
Rubber tread shall have integral riser for the visually impaired, round raised.

ARCHITECTURAL - PLANS

7. Refer to Sheet A104b:
Floor stripping to be provided by flooring manufacturer.

ELECTRICAL:

8. Clarification:
The Electrical Contractor shall include all monitoring charges of the two (2) construction site cameras throughout construction to the end of the job.

PRIOR APPROVALS:

THE FOLLOWING APPROVALS ARE GRANTED IN TRADE NAME FOR BIDDING PURPOSES ONLY. ALL APPROVALS ARE STILL SUBJECT TO ALL CONDITIONS OF THE SPECIFICATIONS UNLESS STATED OTHERWISE HEREIN.

Architectural

Section

06200 Millwork

Manufacturer

Tippen's Specialty Millwork

Electrical

Fire Alarm System

FIKE CORPORATION

END OF ADDENDUM