



# ELECTRICAL SITE PLAN

SCALE: 1" = 50'-0"

NOTE: ELECT. CONTR. SHALL INSTALL ALL UNDERGROUND CONDUITS FOR SITE LIGHTING BY OTHERS.

- FIXTURE SCHEDULE**
- A 2' x 4' LAY-IN TROFFER FOR GRID CEILING WITH TWO (2) F32T8/SP4 LAMPS, ELECTRONIC BALLAST, WHITE TRIM, ACRYLIC LENS, 277 VOLT, METALUX #26R8-232A-2TV-EB01-U; DAY-BRITE #216232-01-277-2/EB; LITHONIA #26T-232-A12-277-6EB; LSI #6A-232-5D-550-UE; COOPER LIGHTING #26R8-232A-INV-EB01-U
  - B 2' x 4' LAY-IN TROFFER FOR GRID CEILING WITH THREE (3) F32T8/SP4 LAMPS, ELECTRONIC BALLAST, WHITE TRIM, ACRYLIC LENS, 277 VOLT, METALUX #26R8-332A-2TV-EB01-U; DAY-BRITE #216332-01-277-1/3EB; LITHONIA #26T-332-A12-277-1/3-EB; LSI #6A-332-5D-550-UE; COOPER LIGHTING #26R8-332A-INV-EB01-U
  - C 2' x 4' LAY-IN TROFFER FOR GRID CEILING WITH FOUR (4) F32T8/SP4 LAMPS, ELECTRONIC BALLAST, WHITE TRIM, ACRYLIC LENS, 277 VOLT, METALUX #26R8-432A-2TV-EB01-U; DAY-BRITE #21432-01-277-1/4EB; LITHONIA #26T-432-A12-277-1/4-EB; LSI #6A-432-5D-550-UE; COOPER LIGHTING #26R8-432A-INV-EB01-U
  - CI SAME AS 'C' EXCEPT FOR GYPSUM BOARD CEILING; COOPER LIGHTING #26R8-432A-INV-EB01-U/DF-24H-U
  - D 2' x 4' LAY-IN TROFFER FOR GRID CEILING WITH THREE (3) F32T8/SP4 LAMPS, ELECTRONIC BALLAST, WHITE TRIM, LOUISIANA CLASSROOM APPROVED ACRYLIC LENS, 277 VOLT, METALUX #26R8-332A-A125-2TV-EB01-U; DAY-BRITE #216332-01-195T-277-1/3EB; LITHONIA #26T8-3-92-ASLT-277-1/3EB; METALUX #26R8-332A1/150/INV-EB01-U; LSI #6A195T-332-550-UE; COOPER LIGHTING #26R8-332A1/156-INV-EB01-U
  - E 2' x 2' LAY-IN TROFFER FOR GRID CEILING WITH THREE (3) F40/80BX/SPX5 LAMPS, ELECTRONIC BALLAST, WHITE TRIM, LOUISIANA CLASSROOM APPROVED ACRYLIC LENS, 277 VOLT, COOPER LIGHTING #26R8-332A1/156-INV-EB01-U
  - F 4' SURFACE MOUNT STRIP WITH TWO (2) F32T8/SP4 LAMPS, MULTI-TAP ELECTRONIC BALLAST, DAY-BRITE TRIM, ACRYLIC LENS, 277 VOLT, METALUX #55-232-1V-EB01-U; LSI #5232-550-UE; COOPER LIGHTING #55-232-INV-EB01-U
  - G 52" DIAMETER CEILING FAN WITH FIVE (5) BLADES, ANTIQUE WHITE FINISH, WHITE EXTENSION ROD-BOTTOM OF FAN 8'-6" AFF, 120 VOLT, CRAFTMADE #TMC1-AW/AH ROYAL PACIFIC LIGHTING #105D/A/R14/H
  - H SHOWER LIGHT FURNISHED & INSTALLED WITH SHOWER UNIT, CONNECTED BY ELECTRICAL CONTRACTOR
  - K 2' x 2' LAY-IN TROFFER FOR GRID CEILING WITH TWO (2) F11T8/SP4/ECO LAMPS, ELECTRONIC BALLASTS, WHITE TRIM, ACRYLIC PRISMATIC LENS, 277 VOLT, COOPER LIGHTING #26R8-217A-INV-EB01-U
  - L 24" ONE (1) CIRCUIT WHITE TRACK WITH FIVE (5) WHITE FLATBACK CYLINDER FIXTURES, EACH WITH ONE (1) 250 WATT PAR-38 LAMP, COMPLETE WITH FEEDS, CONNECTORS, ETC., 120 VOLT, LITHONIA #LTC-FLTB-PAR38-1H (fixtures) & #L121-1H (rack); HALO #L764P (fixtures) #L650P SERIES (rack); CAPRI #CT12-CT4440; LSI #CF-38-WTR12/14LEP/1C1
  - M 6" DIAMETER RECESSED DOWNLIGHT WITH ONE (1) F24T8/SPX41/A4P VERTICAL LAMP, WHITE TRIM, SILVER (CLEAR) ALZAK REFLECTOR, ELECTRONIC BALLAST, 277 VOLT, DAY-BRITE #CM6-FV26-U-V65; LITHONIA #AFV-26DT1-6AR-277-6EB-TRM; PORTFOLIO #C6032-2E-6000-L1; ATLANTIC #65126E1/2-6610CL; COOPER LIGHTING #P66/V142E/6V
  - N 22" DIAMETER SUSPENDED LOW BAY WITH SIX (6) F510BX/81/A4P/EOL LAMPS, CAST ALUMINUM HOUSING, PRISMATIC ACRYLIC REFLECTOR, CONICAL LENS, ANODIZED METAL FINISH STEPPED DIMMING, ELECTRONIC BALLASTS, HOOK & LOCKING FLIG, 277 VOLT, SPORTLITE #L6-6-1K-22LP-277-35L-HC/PL; GUTH LIGHTING #L6-E-2-4-1-3120H-2-LHCF/277/SCKT
  - O 12' LONG WHITE SURFACE MOUNT TRACK WITH FIVE (5) WHITE ADJUSTABLE HEADS, EACH FIXTURE WITH ONE (1) 150 WATT PAR 38 FLOOD LAMP, COMPLETE WITH CONNECTORS, FEED, SUPPORTS, ETC., 120 VOLT, HALO #L21P/L123P/L142P/L143P (track) & #L1543P (fixture); AMERLUX #XTS SERIES (track) & #RB250PAR (fixture); TIMESQUARE #TSB/G250Q; COOPER LIGHTING #L1543P/L620 SERIES TRACK AND ACCESSORIES
  - P 10' DIAMETER X 26" LONG DECORATIVE PENDANT WITH FOUR (4) F40/80BX/SPX41 LAMPS, ELECTRONIC BALLASTS, STAINLESS STEEL AIRCRAFT GRADE SUSPENSION, ETCHED OPAL ACRYLIC DIFFUSER, STEEL/ALUMINUM BODY/TRIM, 277 VOLT, BETA-CALCO #1446005
  - R 6" DIAMETER RECESSED DOWNLIGHT WITH ONE (1) F24T8/SPX41/A4P VERTICAL LAMP, WHITE TRIM, SILVER (CLEAR) ALZAK REFLECTOR, ELECTRONIC BALLAST, 277 VOLT, DAY-BRITE #CM6-FV32-U-V65; LITHONIA #AFV-32DT1-6AR-277-6EB-TRM; PORTFOLIO #C6032-2E-6000-L1
  - S 4' LONG WALL MOUNT FLUORESCENT WITH UP AND DOWNLIGHT PATTERN, TWO (2) F32T8/SP4 LAMPS, ELECTRONIC BALLAST, ACRYLIC LENS, WHITE FINISH, 120 VOLT, DAY-BRITE #CB232H-120-1/2EB; METALUX #BEU-232-120-EB01; LITHONIA #M-2-32-120-EBB-HH HUBBELL #F101250YAL-B1; LIGHTOLIER #CHX232H120S0

- T 6" DIAMETER RECESSED DOWNLIGHT WITH ONE (1) F42T8/SPX41/A4P VERTICAL LAMP, CENTER TRIM, MATTE DIFFUSE FINISH, ELECTRONIC BALLAST, 277 VOLT, LITHONIA #AFV-42TRT-6-PR-LD-277
  - Q WALL MOUNT VAPOR TIGHT INCANDESCENT WITH 100 WATT A19 AMP, CAST ALUMINUM BODY, GLASS GLOBE, CAST GUARD, 120 VOLT, STONCO #VH16; G.E. #HT10F3DD; FRESCOLITE #12015-100MFF-442; DAY-BRITE #11H-150-B; HALO #H2411/MH1; SPERO #1140-CB3C6
  - X EXIT LIGHT WITH RED LED LAMPS, THERMOPLASTIC HOUSING, 277 VOLT, DAY-BRITE #CLR14; LITHONIA #LGM-54-3-R-120/277; SURE-LITES #L710R/H; LSI #EX1/2-R-110/277; COOPER LIGHTING #L710R/H
  - Z EXTERIOR WALL MOUNT EMERGENCY LIGHT, NET LOCATION LISTED, FINISH AS SELECTED BY THE ARCHITECT, 277 VOLT, LITHONIA #AFNDB; COOPER LIGHTING #AEL115D
  - EA 8" DIAMETER RECESSED OPEN DOWNLIGHT WITH ONE (1) 70 WATT METAL HALIDE LAMP, HIGH POWER FACTOR BALLAST, CLEAR ALZAK REFLECTOR, SUITABLE FOR DAMP LOCATION, 277 VOLT, LITHONIA #LPH-10M-120-802A2; FEACHTREE #F0M4Z-8070-C; PORTFOLIO #M1800T-130-43800C; CAPRI #CM6-M10-V82; LITON #LH18070-E-81TC; COOPER LIGHTING #P71A102E/7V
  - EB 16-1/2" WIDE X 8-1/4" HIGH X 4" PROJECTION ROUNDED WEDGE WITH ONE (1) 175 WATT METAL HALIDE LAMP, HFF BALLAST, DIE-CAST ALUMINUM HOUSING, WIDE-THROW DISTRIBUTION, FINISH AS SELECTED BY ARCHITECT, NET LOCATION LISTED, 277 VOLT, MCPHILBEN #102-MT-15MH-277-FINISH; KIM #ND14D277-M4277-FINISH-A-30; GREEN LEE LIGHTING #V65-15MH-HF-C7B5; LITHONIA #FL2-15MH-R4-277-FINISH; LSI #C4W6-3-15MH-F-MT-FINISH; EXCELLINE #6501234L1-FINISH
  - EC 16" WIDE X 4" HIGH ROUNDED GROUND MOUNTED FLAG POLE FLOODLIGHT ONE (1) 175 WATT METAL HALIDE LAMP, VERTICAL LAMP, NARROW SPOT DISTRIBUTION, HIGH POWER FACTOR BALLAST, WITH STANCHION MOUNT IN 12" DIAMETER X 12" DEEP CONCRETE FOOTING, DIE-CAST ALUMINUM HOUSING, TEMPERED GLASS LENS, 277 VOLT, LITHONIA #AF1-15M-SP-277-AF15MTHK-LP1; INVE #VFS-K-15-MH-MT-NS-FINISH-L5M-FINISH; GARDCO #DFT-SP-15MH-277-FINISH; LSI #DPS-SP15-MH-F-MT-FINISH-BKA-DR2-5M-C-29-FINISH; COOPER LIGHTING #VFS-K-15-MH-MT-NS-FINISH/54-FINISH
  - ED 12" WIDE X 26" HIGH WALL SCONCE WITH TWO (2) F32T8/SP4/RS LAMPS, OPAL ACRYLIC DIFFUSER, STAINLESS STEEL COVER, STEEL/CAST ALUMINUM BODY, FINISH AS SELECTED BY ARCHITECT, HFF BALLAST, NET LOCATION LISTED, 120 VOLT, BETA-CALCO #B1-2034-FINISH; VISA #V1042-277-120-FIN; SCOTT LAMP CO. #5106-2CF34-FINISH-2TV
  - EE 14" DIAMETER WALL MOUNT SCONCE WITH ONE (1) F42T8/SPX41/A4P LAMP, DIE-CAST ALUMINUM HOUSING, BOROSILICATE GLASS LENS, FINISH AS SELECTED BY ARCHITECT, ELECTRONIC BALLAST, NET LOCATION LISTED, 277 VOLT, LITHONIA #VGR2-42TRT-8L-MVOLT-FINISH-ADCF-LP1
  - EF WALL PACK FLOOD WITH ONE (1) 100 WATT METAL HALIDE LAMP, HFF BALLAST, DIE-CAST ALUMINUM HOUSING, PRISMATIC GLASS LENS, BUILT-IN PHOTOELECTRIC CELL, 277 VOLT, DAY-BRITE #M10-M1-2P-FE; H-TEK #THH-100M-277-FE; LUMARK #MHL-100-MT-FE; COOPER LIGHTING #MHL-100-MT-FE
  - EG 6" SQUARE, 30" LONG STRAIGHT STEEL POLE WITH THREE (3) 400 WATT METAL HALIDE FLOODLIGHTS, POLE FURNISHED WITH BOLT COVER, HFF BALLAST, TEMPERED GLASS LENS, FINISH AS SELECTED BY THE ARCHITECT, 277 VOLT, DAY-BRITE #FL40M4H-277E/SP (fixtures), K1H POLES #55P30-5-0-T-FINISH-D13100-B0 (pole); LUMARK #3) #MNR-655-400-MT-FB271 (fixtures) & #MCRVAN EDISON #5555A-50SP101-23 (pole); LITHONIA #TR-400M-TA-277-15-938 (fixtures) & LITHONIA #5550-65-120-DDB (pole); COOPER LIGHTING #MNR-655-400-MT-L1; COOPER LIGHTING #101-A23; K1 INDUSTRIES #55P30-6-0-T-BZ-2/FA310-ES0-2-BR-2
  - EH SITE LIGHTING POLE/FIXTURE FURNISHED & INSTALLED BY GLECO
  - EK 8" DIAMETER RECESSED OPEN DOWNLIGHT WITH ONE (1) 100 WATT METAL HALIDE LAMP, HIGH POWER FACTOR BALLAST, CLEAR ALZAK REFLECTOR, SUITABLE FOR DAMP LOCATION, 277 VOLT, CAPRI #R14-1052M-277V; PORTFOLIO #M1800T-140-44800C-277; LITHONIA #LPH-100H-277-603A; FEACHTREE #F4HX-8100-CL-277; PATHWAY #H1100-CF7110; DAYBRITE #CM8-M100-V82
  - EL WALL MOUNT ADJUSTABLE ARCHITECTURAL FLOOD LIGHT WITH ONE (1) 100 WATT METAL HALIDE LAMP, HFF BALLAST, WIDE FLOOD, NATURAL ALUMINUM FINISH, 277 VOLT, LITHONIA #ASH100H-VDF-277-AF14A-DNAT
- NOTE: FURNISH AND INSTALL A WIRE GUARD OVER ALL TYPE 'X' EXIT LIGHTS LOCATED IN THE GYMNASIUM.

- POWER PLAN KEYNOTES**
- 1 LOCATE DEVICE(S) ABOVE THE COUNTERTOP AT THIS MILLWORK UNLESS NOTED OTHERWISE.
  - 2 LOCATE DUPLEX RECEPTACLE AND CABLE TV OUTLET 1' AFF.
  - 3 LOCATE DUPLEX RECEPTACLE FOR GYMNASIUM/CAFETERIA INTERCOM SYSTEM CONSOLE.
  - 4 LOCATE DUPLEX RECEPTACLE, DATA OUTLET & CABLE TV OUTLET FLUSH IN FLOOR.
  - 5 LOCATE DUPLEX RECEPTACLE BEHIND ENG; COORDINATE EXACT LOCATION WITH THE PLUMBING CONTRACTOR.
  - 6 LOCATE DUPLEX RECEPTACLE 24" AFF FOR WASHER.
  - 7 LOCATE A 250 VOLT, 30 AMP, 2 POLE, 3 WIRE SINGLE RECEPTACLE (NEMA 6-30R) 24" AFF FOR DRYER.
  - 8 LOCATE A DUPLEX RECEPTACLE 36" AFF FOR REFRIGERATOR.
  - 9 ELECT. CONTR. SHALL FURNISH & CONNECT 120 VOLT POWER & DATA OUTLET FOR BUILDING EMS; COORDINATE WITH MECH. CONTR.
  - 10 LOCATE J-BOX 48" AFF FOR HAND DRYER.
  - 11 LOCATE DUPLEX RECEPTACLE AND VOICE/DATA OUTLET 24" AFF FOR COPY MACHINE.
  - 12 LOCATE DUPLEX RECEPTACLE AND DATA OUTLET FLUSH IN FLOOR.
  - 13 LOCATE DUPLEX RECEPTACLE 36" AFF FOR VENDING MACHINE.
  - 14 LOCATE DUPLEX RECEPTACLE 48" AFF.
  - 15 3/4" PLYWOOD TELEPHONE BACKBOARD ROUTE ON THREE (3) WALLS; ROUTE A #6 AWG BARE COPPER GROUND WIRE ALONG BOTTOM OF BACKBOARD AND ROUTE TO GROUND BUS OF PANEL. CONDUCTOR ON MAIN TELEPHONE BACKBOARD IN DATA 120.
  - 16 ROUTE A 1/2", 2#12 THHN & #12 GND. TO CORRESPONDING ECU LOCATED ON THE EXTERIOR OF THE BUILDING.
  - 17 LOCATE DUPLEX RECEPTACLE ABOVE THE CEILING FOR PROJECTOR.
  - 18 LOCATE DUPLEX RECEPTACLE 6'-0" AFF IN CABINET FOR AMPLIFIER.
  - 19 LOCATE A 250 VOLT, 30 AMP, 3 POLE, 4 WIRE SINGLE RECEPTACLE (NEMA 15-50R) 24" AFF FOR KILN-208V/3P, 31-TLA.
  - 20 LOCATE DUPLEX RECEPTACLE FOR HOT WATER CIRCULATING PUMP; COORDINATE EXACT LOCATION WITH PLUMBING CONTRACTOR.
  - 21 LOCATE A 250 VOLT, 30 AMP, 2 POLE, 3 WIRE SINGLE THIST-LOCK RECEPTACLE (NEMA L6-30R) 24" AFF FOR DATA RACK.
  - 22 LOCATE A 4" SQUARE J-BOX FOR BASKETBALL GOAL HINGE AT THE CEILING WITHIN 3' OF THE HINGE LOCK. THIS IS TO BE FURNISHED BY MANUFACTURER, INSTALLED, AND CONNECTED BY THE ELECTRICAL CONTRACTOR. COORDINATE EXACT LOCATION WITH THE MANUFACTURER/INSTALLER.
  - 23 TWO (2) GANGED KEY SWITCHES FOR CONTROL OF BASKETBALL GOALS; FURNISHED BY THE MANUFACTURER, INSTALLED AND CONNECTED BY THE ELECTRICAL CONTRACTOR. COORDINATE SIZE OF BOX FOR SWITCHES & EXACT REQUIREMENTS WITH THE MANUFACTURER/INSTALLER.
  - 24 ROUTE A 1/2", 2#18 THHN CONTROL WIRES FOR CONTROL, SEE KEYNOTE 23.
  - 25 PARTITION KEY CONTROL STATION FURNISHED BY PARTITION INSTALLER, INSTALLED & CONNECTED BY ELECTRICAL CONTRACTOR.
  - 26 PARTITION POWER UNIT - 120V; ROUTE WIRING CONCEALED IN WALL WHERE POSSIBLE.
  - 27 ROUTE A 1/2", 2#18 THHN CONTROL WIRES TO PARTITION POWER UNIT.
  - 28 LOCATE DUPLEX RECEPTACLE FOR WATER HEATER; COORDINATE EXACT LOCATION WITH PLUMBING CONTRACTOR.
  - 29 LOCATE QUADRUPLEX RECEPTACLE & DATA OUTLET FLUSH IN FLOOR.
  - 30 LOCATE DUPLEX RECEPTACLE (FOR ELEVATOR PIT SUMP PUMP), TYPE 'G' LIGHT FIXTURE & SWITCH IN ELEVATOR PIT.
  - 31 LOCATE DUPLEX RECEPTACLE 24" AFF FOR ICE MACHINE.
  - 32 LOCATE A 125 VOLT, 50 AMP, 2 POLE, 3 WIRE SINGLE RECEPTACLE (NEMA 5-50R) INSIDE OF CABINET FOR HW.
  - 33 LOCATE A 600 VOLT, 40 AMP, 3 POLE SHUNT TRIP BREAKER 48" AFF FOR CONNECTION TO ELEVATOR CONTROLLER-480V/3P, 15HP.
  - 34 LOCATE A 125 VOLT, 20 AMP, 1 POLE SHUNT TRIP BREAKER 48" AFF FOR ELEVATOR CAB LIGHTS.
  - 35 MOTORIZED PROJECTION SCREEN & CONTROL SWITCH; PROJECTION SCREEN FURNISHED & INSTALLED BY OTHERS, CONTROL SWITCH FURNISHED BY OTHERS, INSTALLED & CONNECTED BY ELECT. CONTR.
  - 36 ROUTE CONDUIT & WIRING FOR SERVICE TO CU-1 CONCEALED INSIDE OF THE WALL.
  - 37 LOCATE DUPLEX RECEPTACLE & DATA OUTLET ABOVE THE CEILING FOR PROJECTOR.
  - 38 LOCATE VOICE OUTLET 48" AFF.
  - 39 LOCATE DUPLEX RECEPTACLE IN UPPER CABINET MILLWORK FOR MICROWAVE; COORDINATE EXACT LOCATION WITH THE ARCHITECT.
  - 40 LOCATE DUPLEX RECEPTACLE & CABLE TV OUTLET IN CEILING FOR TELEVISION.
  - 41 TEMPERATURE CONTROL POWER MONITOR PANEL, COORDINATE EXACT LOCATION WITH MECH. CONTR.
  - 42 LOCATE A 125 VOLT, 30 AMP, 2 POLE, 3 WIRE SINGLE RECEPTACLE (NEMA 6-30R) 24" AFF FOR DRYER.

SYMBOL SCHEDULE	
Ⓜ	FLUORESCENT FIXTURE; "A" DENOTES TYPE
Ⓞ	INCANDESCENT OR H.I.D. FIXTURE; "B" DENOTES TYPE
Ⓛ	LIGHT FIXTURE ON EMERGENCY POWER
Ⓛ	TRACK LIGHTING
Ⓛ	EXIT LIGHT
Ⓛ	DUPLEX RECEPTACLE
Ⓛ	GROUND FAULT INTERRUPTER DUPLEX RECEPTACLE
Ⓛ	DUPLEX RECEPTACLE ON EMERGENCY POWER
Ⓛ	QUADRUPLEX RECEPTACLE
Ⓛ	SPECIAL RECEPTACLE
Ⓛ	WEATHERPROOF
Ⓛ	NIGHT LIGHT
Ⓛ	SINGLE POLE TOGGLE SWITCH
Ⓛ	FAN SPEED CONTROLLER
Ⓛ	LOW-VOLTAGE LIGHT SWITCH
Ⓛ	WALL MOUNTED OCCUPANCY SENSOR
Ⓛ	CONDUIT IN WALL OR CEILING; DASHES DENOTE NO. OF WIRES
Ⓛ	CONDUIT BELOW SLAB; DASHES DENOTE NO. OF WIRES
Ⓛ	HOMERUN; DASHES DENOTE NO. OF WIRES
Ⓛ	POWER PANEL
Ⓛ	FUSED SAFETY DISCONNECT SWITCH
Ⓛ	MOTOR
Ⓛ	DATA OUTLET
Ⓛ	DATA/DATA OUTLET
Ⓛ	VOICE/DATA OUTLET
Ⓛ	WALL CLOAK
Ⓛ	CABLE TV OUTLET
Ⓛ	JUNCTION BOX
Ⓛ	KEYNOTE
Ⓛ	CEILING MOUNTED OCCUPANCY SENSOR
Ⓛ	FIRE ALARM SYSTEM PULL STATION
Ⓛ	FIRE ALARM SYSTEM SPEAKER/STROBE
Ⓛ	FIRE ALARM SYSTEM CEILING MOUNT STROBE
Ⓛ	FIRE ALARM SYSTEM CEILING MOUNT HORN/STROBE
Ⓛ	FIRE ALARM SYSTEM CEILING MOUNT SPEAKER/STROBE
Ⓛ	FIRE ALARM SYSTEM SMOKE DETECTOR
Ⓛ	FIRE ALARM SYSTEM THERMAL DETECTOR
Ⓛ	INTERCOM SYSTEM PRIVACY HANDESET
Ⓛ	INTERCOM SYSTEM CALL-IN SWITCH WITH EMERGENCY OVER-RIDE
Ⓛ	INTERCOM SYSTEM SPEAKER
Ⓛ	WALL MOUNT MICROPHONE OUTLET
Ⓛ	FLOOR MICROPHONE OUTLET
Ⓛ	INTERCOM SYSTEM MASTER CONTROL STATION
Ⓛ	SECURITY SYSTEM CAMERA
Ⓛ	CLASSROOM AUDIO SYSTEM SPEAKER
Ⓛ	CLASSROOM AUDIO SYSTEM CEILING MOUNT INFRARED SENSOR
Ⓛ	SPEAKER VOLUME CONTROLLER
Ⓛ	VARIABLE FREQUENCY DRIVE
Ⓛ	PYLON SIGN DUCT DETECTOR
Ⓛ	DOOR HOLD OPEN DEVICE
Ⓛ	SECURITY SYSTEM KEYPAD
Ⓛ	INTERCOM SYSTEM EXTERIOR SPEAKER

ANDREW GASAWAY, JR., ARCHITECT, AIA, APA  
 BRETT GASAWAY, ARCHITECT, AIA, NCARB  
 CHRIS BANKSTON, ARCHITECT, AIA, NCARB, LEED AP

**GGB**  
 Gasaway | Gasaway | Bankston  
 Architects + Planners

1007 W. THOMAS ST., SUITE G  
 HAMMOND, LA 70401  
 985.345.5047  
 985.345.5260  
 FAX 985.345.5260

JOSEPH B. LANCASTER  
 ELEMENTARY SCHOOL  
 ST. TAMMANY PARISH SCHOOL BOARD  
 MADISONVILLE, LOUISIANA  
 ST/98 PROJECT #0825

THIS DRAWING IS AN INSTRUMENT OF SERVICE, IS AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT AND SHALL NOT BE REPRODUCED, PUBLISHED OR USED IN ANY WAY WITHOUT THE EXPRESS PERMISSION OF THE ARCHITECT.

PROJ. NO. **0825**  
 DATE **06.25.09**

PROFESSIONAL SEAL OF ARCHITECT AND PLANNER  
 DANIEL T. CALONGONE  
 REG. NO. 15220  
 REGISTERED PROFESSIONAL ARCHITECT AND PLANNER  
 STATE OF LOUISIANA

AS Daniel Calongone & Associates  
 7811 Winwood Blvd., Suite D  
 Baton Rouge, Louisiana 70809  
 (504) 222-9223 fax (504) 222-9414

**E100**