



BEAM SCHEDULE	
MARK	BEAM
B-1	* 2-2X10 W/ 1/2" SEPARATION
B-2	* 2-2X12 W/ 1/2" SEPARATION
B-3	LAMINATED BEAM (3 1/2" X 8 1/4")
B-4	2-2x12 NAILED @ 16" O.C. STAGGERED LAMINATED BEAM (3 1/2" X 8 1/4")

* ALL HEADERS SHALL HAVE 1/2" SOLID PLYWOOD BETWEEN

NOTES:
 1. BEAM SIZES ARE BASED ON CATALOG INFORMATION FROM "ANTHONY POWER BEAMS" LSL, 2400 Fb - 1.8E
 2. SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS

LEASING OFFICE 1 ST FLOOR FRAMING PLAN
 SCALE: 1/4" = 1'-0"

THE BRYAN COMPANY ISLAND PARK APARTMENT COMMUNITY SHREVEPORT, LA.	<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;"> <p>ISLAND PARK</p> <p>DAMMON ENGINEERING INC.</p> <p>ARCHITECTS - ENGINEERS</p> <p>819 ROBERT ROAD SLIDELL, LA. 70458</p> </div> <div style="text-align: center;"> <p>ISLAND PARK</p> <p>DAMMON ENGINEERING INC.</p> <p>ARCHITECTS - ENGINEERS</p> <p>819 ROBERT ROAD SLIDELL, LA. 70458</p> </div> </div>
SCALE: AS NOTED	FILE: -
JOB No.: -	DATE: 03-29-04
SHEET	S-3
OF -	