



BEAM SCHEDULE	
MARK	BEAM
B-1	* 2-2X10 W/ 1/2" SEPARATION
B-2	* 2-2X12 W/ 1/2" SEPARATION
B-3	LAMINATED BEAM (3 1/2" X 8 1/4 ")
B-4	2-2x12 NAILED @ 16" O.C. STAGGERED
ALTERNATE	LAMINATED BEAM (3 1/2" X 8 1/4")

* ALL HEADERS SHALL HAVE 1/2" SOLID PLYWOOD BETWEEN

NOTES:
 1. BEAM SIZES ARE BASED ON CATALOG INFORMATION FROM "ANTHONY POWER BEAMS" LSL, 2400 Fb - 1.8E
 2. SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS

LEASING OFFICE 2ND FLOOR FRAMING & ROOF PLAN
 SCALE: 1/4" = 1'-0"

THE BRYAN COMPANY
 ISLAND PARK
 APARTMENT COMMUNITY
 SHREVEPORT, LA.

ISLAND PARK
DAMMON ENGINEERING INC.
 ARCHITECTS - ENGINEERS
 819 ROBERT ROAD
 SLIDELL, LA. 70458

SCALE: AS NOTED
 FILE: -
 JOB No.: -
 DATE: 03-29-04
 SHEET
S-4
 OF -