



LEGEND

- SUPPLY AIR VENT
- ⚡ FIRE DAMPER
- BATHROOM EXHAUST
- ⊕ THERMOSTAT

MECHANICAL SPECIFICATIONS
3 TON HEAT PUMP

EQUIPMENT SELECTIONS

INDOOR HEAT PUMP	ADP BU3610
AIR FLOW	1200 CFM
ELECTRICAL SPECIFICATIONS	240V-1ϕ
UNIT M.C.A. (INCLUDING HEAT)	60.0 AMPS
REV. CYCLE HEAT CAPACITY	34120 BTUH
AUX. HEAT CAPACITY	10.0 KW (41.6A)
OUTDOOR HEAT PUMP	DUCANE HP10B36
ELECTRICAL SPECIFICATIONS	240V-1ϕ
UNIT M.C.A.	23.9 MCA
COOLING CAPACITY	34,400 BTUH S.E.E.R. 10.0

MECHANICAL SPECIFICATIONS
4 TON HEAT PUMP

EQUIPMENT SELECTIONS

INDOOR HEAT PUMP	DUCANE DBP48CA
AIR FLOW	1600 CFM
ELECTRICAL SPECIFICATIONS	240V-1ϕ
UNIT M.C.A. (INCLUDING HEAT)	60.0 AMPS
REV. CYCLE HEAT CAPACITY	47,000 BTUH
AUX. HEAT CAPACITY	10.0 KW
OUTDOOR HEAT PUMP	DUCANE HP10B48
ELECTRICAL SPECIFICATIONS	240V-1ϕ
UNIT M.C.A.	32.2 MCA
COOLING CAPACITY	45,500 BTUH S.E.E.R. 10.0

SECOND FLOOR LEASING OFFICE HVAC PLAN
SCALE: 1/4" = 1'-0"

THE BRYAN COMPANY
ISLAND PARK
APARTMENT COMMUNITY
SHREVEPORT, LA.

ISLAND PARK
DAMMON ENGINEERING INC.
ARCHITECTS - ENGINEERS
819 ROBERT ROAD
SLIDELL, LA. 70458

SCALE: AS NOTED

FILE: -

JOB No.: -

DATE: 03-29-04

SHEET

M-2

OF -