

REVISED

GA FILE NO. WP 3370


GENERIC

ONE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR GYPSUM VENEER
BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE OF
DOUBLE ROW OF 2x4 WOOD STUDS 16" O.C. ON SEPERATE PLATES
1-1/2" APART WITH 6D COATED NAILS, 1-7/8" LONG, 0.0915"
SHANK, 1/4" HEADS, 7" O.C.



JOINTS STAGGERED 16" ON OPPOSITE SIDES. HORIZONTAL BRACING
REQUIRED AT MID HEIGHT. (LOAD BEARING)

DETAIL

N.T.S.



1 HOUR FIRE 45 TO 49 STC SOUND



THICKNESS:
APPROX. WEIGHT:
FIRE TEST:

10-1/4"

8 PSF

SEE WP 3605

(UL R1319-4, 6, 6-17-52;
UL R2717-39, 1-20-66;
UL R3501-52, 3-15-66;
UL DESIGN U305;
ULC DESIGN W301)
ESTIMATED

SOUND TEST: