


FLOOR PLAN
SCALE: 1/4" = 1'



GA FILE NO. WP 1072 GENERIC

ONE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR GYPSUM VENEER BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE OF 3.58" STEEL STUDS 24" O.C. WITH 1" TYP. SPRING WALL SCREWS 8" O.C. AT VERTICAL STUDS AND 12" O.C. AT FLOOR AND CEILING RUNNERS AND INTERMEDIATE STUDS
JOINTS STAGGERED 24" ON EACH SIDE AND ON OPPOSITE SIDES. SOUND BRANDED
SOUND TEST:

1 HOUR FIRE 45 TO 49 STC SOUND
THICKNESS: 4.78"
APPROX. WEIGHT: 6.98 LBS/SQ. FT.
FIRE TEST: FM 1995-51-1888; CSU 1-1770; I-641; UL C-797484; 791500; 791847; 81-251 (ULC DESIGNATION W-19); IMC2015 (SNV); 2-2531



DAMMON ENGINEERING, INC.
CHIEF ENGINEER
ENMETT DAMMON, P.E.
CHIEF ARCHITECT
ROBERT WILTSE

554 OLD SPANISH TRAIL
SLIDELL, LA, 70458
OFFICE: 985-649-5932
FAX: 985-641-5930

WWW.DAMMONENGINEERING.COM
WEBSITE:
E-MAIL:
DAMMONENG@BELLCSOUTH.NET

ARCHITECTURE
ENGINEERING
STUDIES
PLANNING
INVESTIGATION
EXPERT WITNESS

NEW
CHURCH
FIRST BAPTIST
CHURCH
64541 HWY 3081
PEARL RIVER, LA
70452

FLOOR
PLAN

REV:

SCALE: AS NOTED

JOB#: 2108

DATE: 04-26-11

SHEET 3

A-1

OF 14