



LUMINAIRE SCHEDULE

Label	Catalog Number	Description	Lamp
F1	B6 / B632P WH ELITE LIGHTING	6" RECESSED BLACK BAFFLE DOWNLIGHT, WHITE TRIM FLANGE	90PAR/H/FL25 130V
F2	2AV G 2 32 MDR 2X4 AVANTE, LITHONIA LIGHTING	RECESSED LAYIN, METAL DIFFUSER W/ROUND PERFORATIONS BACKED W/ ACRYLIC OVERLAY	TWO 32-WATT T8 LINEAR FLUORESCENT.
F3	8VF 1/42TRI MVOLT 802AZ TRW LITHONIA LIGHTING	8" OPEN DOWNLIGHT, SPECULAR REFLECTOR, WHITE TRIM FLANGE	ONE 42-WATT TRIPLE TUBE COMPACT FLUORESCENT, VERTICAL BASE-UP POSITION.
F4	2GT8 3 32 A12 MVOLT 1/3 GEBI0IS LITHONIA LIGHTING	G18 GENERAL PURPOSE T8 TROFFER 2X4' 3 LP T8 #A12 LENS 1/3 ELECTRONIC BALLST	THREE 32-WATT T8 LINEAR FLUORESCENT.
F5	2PM3N 3 32 18LD MVOLT 1/3 GEBI0IS LITHONIA LIGHTING	PARAMAX PARABOLIC TROFFER 3' LVR 2'X4' LP T8 18-CELL L0 18R SEMI-SPEC LVR 1/3 ELECTRONIC BALLAST	THREE 32-WATT T8 LINEAR FLUORESCENT.
F6	SB 2 32 MVOLT GEBI0IS LITHONIA LIGHTING	SQUARE BASKET WRAP, 8 3/8" 2LP T8 PRISMATIC ELECTRONIC BALLAST	TWO 32-WATT T8 LINEAR FLUORESCENT.
F7	WC 2 32 MVOLT GEBI0IS LITHONIA LIGHTING	COMMERCIAL WALL BRACKET 4' 2 LAMP T8 ELECTRONIC BALLAST	TWO 32-WATT T8 LINEAR FLUORESCENT.
F8	Z 1 32 MVOLT Z8ASR48 GEBI0IS LITHONIA LIGHTING	NEW ONE LAMP-32W-T8 STRIP WITH ASYMMETRIC REFLECTOR.	ONE 32-WATT LINEAR FLUORESCENT T8, HORIZONTAL POS.
F9	FTM 100M TA TB LITHONIA LIGHTING	SPECIFICATION FLOODLIGHT, TA DISTRIBUTION, 100W MH, W/ CLEAR LAMP.	ONE 100-WATT CLEAR ED-17 METAL HALIDE, VERTICAL BASE-DOWN POSITION.
F10	TWP 150M TB LPI LITHONIA LIGHTING	GENERAL PURPOSE BUILDING MOUNTED LUMINAIRE, 150W MH, W/ CLEAR LAMP.	ONE 150-WATT CLEAR ED-28 METAL HALIDE, HORIZONTAL POSITION.
F11	9860 LEVITON	CEILING MOUNTED COMPACT FLYURESCCENT KEYLESS	ONE 13-WATT GU24
EX	XE 2 R W EM EELP LIGHTING	WHITE THERMOPLASTIC LED EXIT SIGN, RED LETTERING, BATTERY INCLUDED	LED
EM	EM1 EELP LIGHTING	WHITE THERMOPLASTIC TWO HEAD EMERGENCY	TWO 54-WATT
EM1	DEM WH EELP LIGHTING	WET LOCATION LISTED WALL MOUNTED EMERGENCY EGRESS LIGHT	TWO 6-WATT ZENON