



**POWER PLAN PHASE A**  
SCALE: 1/8"=1'-0"

**GENERAL ELEC  
POWER NOTES**

1. ALL WORK SHALL CONFORM TO THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE, THE GOVERNING ELECTRICAL CODE AND ALL OTHER INSPECTION DEPARTMENT'S HAVING JURISDICTION. CERTAIN CERTIFICATES OR APPROVALS MAY BE REQUIRED. ELECTRICAL CONTRACTOR SHALL VERIFY ALL WIRE AND CONDUIT SIZES FOR MECHANICAL EQUIPMENT TO BE INSTALLED.
2. ALL MATERIALS FURNISHED SHALL BE NEW AND SHALL BE U.L. LISTED. THE DRAWINGS INDICATE SIZE AND GENERAL LOCATION OF WORK. SCALE DIMENSIONS SHALL NOT BE USED. THE EXACT LOCATION OF ALL LIGHTING FIXTURES, RECEPTACLES AND TELEPHONE OUTLETS, ETC., SHALL BE DETERMINED BY ACTUAL CONDITIONS IN THE FIELD.
3. PRIOR TO BEGING, CONTRACTOR SHALL VISIT THE JOB SITE AND FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS.
4. ELECTRICAL CONTRACTOR SHALL COORDINATE HIS WORK WITH OTHER CONTRACTORS WHOSE WORK MAY AFFECT THIS INSTALLATION.
5. ELECTRICAL CONTRACTOR SHALL CORRECTIVE REPAIRS NECESSARY TO BRING EXISTING ELECTRICAL SYSTEMS INTO COMPLIANCE WITH THE NATIONAL ELECTRICAL CODE AND THE GENERAL CONTRACTOR.
6. ELECTRICAL CONTRACTOR SHALL CORRECTIVE REPAIRS NECESSARY TO BRING EXISTING ELECTRICAL SYSTEMS INTO COMPLIANCE WITH THE NATIONAL ELECTRICAL CODE AND THE GENERAL CONTRACTOR.
7. ELECTRICAL CONTRACTOR SHALL CORRECTIVE REPAIRS NECESSARY TO BRING EXISTING ELECTRICAL SYSTEMS INTO COMPLIANCE WITH THE NATIONAL ELECTRICAL CODE AND THE GENERAL CONTRACTOR.
8. WHERE MORE THAN ONE SWITCH OCCURS IN THE SAME LOCATION, THEY SHALL BE INSTALLED IN A GANG TYPE BOX UNDER ONE COVER PLATE.
9. ELECTRICAL CONTRACTOR, BEFORE INSTALLING ANY OF THE WORK, SHALL SEE THAT IT DOES NOT INTERFERE WITH CLEARANCES REQUIRED FOR FINISHED CEILING, HUNG CEILING, PLASTER PARTITIONS, WALLS, ETC. AS SHOWN IN THE ARCHITECTURAL DRAWINGS AND DETAILS. IF ANY INTERFERENCE IS ENCOUNTERED, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT IMMEDIATELY. THE CONTRACTOR SHALL NOT BE RESPONSIBLE FOR ANY DAMAGE TO THE ARCHITECT'S WORK OR EXPENSE SHALL MAKE SUCH CHANGES IN THE WORK AS DIRECTED BY THE ARCHITECT, AS WELL AS TO PERMIT THE INSTALLATION OF THE ARCHITECTURAL WORK AS SHOWN ON THE PLANS AND DETAILS.
10. PERFORM TEST REQUIRED BY THE OWNER OR THE ENGINEER IN CONNECTION WITH THE OPERATION OF THE ELECTRICAL SYSTEM IN THE BUILDING. ALL TESTS SHALL BE MADE IN ACCORDANCE WITH THE LATEST EDITION OF THE IEEE AND THE NATIONAL ELECTRICAL CODE.
11. MINIMUM CONDUCTOR SIZE SHALL BE #12, 600V INSULATION MINIMUM SIZE CONDUIT SHALL BE 3/4" ELECTRICAL METAL (EIM) TYPE EMT FOR NON-METALLIC CABLE (NMC) LABEL COPPER FOR LIGHTS AND RECEPTACLE CIRCUITS IN WOOD FRAME CONSTRUCTION AREAS ONLY. IN STEEL FRAMING AREAS THE USE OF EMT (MINIMUM) IS REQUIRED. EXTERIOR FITTINGS SHALL BE CAST BOXES AND COVERS. INTERIOR FITTINGS SHALL BE STAMPED BOXES.
12. CONTRACTOR SHALL INSTALL WIRING AND OTHER CIRCUIT COMPONENTS TO MATCH EQUIPMENT ACTUALLY INSTALLED.
13. INSTALL GROUND FAULT RECEPTACLES AT RECEPTACLE LOCATIONS WITHIN 5' OF SINKS OR LAVATORIES, AND AT EXTERIOR LOCATIONS. EXTERIOR RECEPTACLES SHALL ALSO BE WATERPROOF.
14. BONDING AND GROUNDING SHALL BE IN ACCORDANCE WITH NFPA 70:230-63, NFPA 70:250-23, 250-71 & 250-72.
15. GROUND NEUTRAL IN ACCORDANCE WITH NFPA 70:250-230.
16. FIRES SHALL BE IT CLASS 95, 250 VOLT, 200,000 AMP INTERRUPTING CAP.
17. PROVIDE SERVICES OF A FIRE/SMOKE DETECTION AND ALARM COMPANY TO DESIGN AND INSTALL ALARM SYSTEM TO MEET REQUIREMENTS OF THE STATE FIRE MARSHALL AND THE FIRE DISTRICT.
18. EXTERIOR LIGHTING SHALL BE SHAVED OR INWARDLY DIRECTED IN SUCH A MANNER AS TO NOT BE A HAZARD TO TRAFFIC OR PEDESTRIANS. LIGHTS SHALL BE PROTECTED BY GROUNDING AND GROUNDING SHALL EXCEED ONE FOOT CANDLE AS MEASURED AT THE ABUTTING PROPERTY LINE.
19. ALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATIONS THROUGH PARTITIONS SHALL BE FIRE CALKED. PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM E814.
20. VERIFY ELECTRICAL CONNECTIONS PER MANUFACTURERS RECOMMENDATIONS.

**LEGEND**

- |  |  |
|--|--|
| SYMB DESCRIPTION   | 120V DUPLEX RECEPTACLE - FLOOR MOUNTED   |
| 120V DUPLEX RECEPTACLE - FLOOR MOUNTED   | 120V DUPLEX RECEPTACLE - ABOVE COUNTER HT.   |
| 120V DUPLEX RECEPTACLE - ABOVE COUNTER HT.   | 120V DUPLEX RECEPTACLE - REFER TO PANEL SCHEDULE FOR CIRCUIT SIZE                    |
| 120V DUPLEX RECEPTACLE - REFER TO PANEL SCHEDULE FOR CIRCUIT SIZE                    | 60V DUPLEX RECEPTACLE  |
| 60V DUPLEX RECEPTACLE  | 60V QUAD RECEPTACLE  |
| 60V QUAD RECEPTACLE  | 220V ELECTRIC DRYER RECEPTACLE - MOUNTED AT 30' AFF                                  |
| 220V ELECTRIC DRYER RECEPTACLE - MOUNTED AT 30' AFF                                  | 220V DEDICATED 60V RECEPTACLE  |
| 220V DEDICATED 60V RECEPTACLE  | VENTILATION-ROOF (VRC) DUPLEX RECEPTACLE MOUNTED AT 30' AFF (UNLESS OTHERWISE NOTED) |
| VENTILATION-ROOF (VRC) DUPLEX RECEPTACLE MOUNTED AT 30' AFF (UNLESS OTHERWISE NOTED) | STANDARD 120V DUPLEX RECEPTACLE - FLOOR MOUNTED                                      |
| STANDARD 120V DUPLEX RECEPTACLE - FLOOR MOUNTED                                      | STANDARD 120V DUPLEX RECEPTACLE - WALL MOUNTED                                       |
| STANDARD 120V DUPLEX RECEPTACLE - WALL MOUNTED                                       | STANDARD 120V DUPLEX RECEPTACLE - FLOOR MOUNTED                                      |
| STANDARD 120V DUPLEX RECEPTACLE - FLOOR MOUNTED                                      | 125V 15 AMP DUPLEX-USB 5VDC 3 AMP HUBBELL USB CHARGER RECEPTACLE                     |
| 125V 15 AMP DUPLEX-USB 5VDC 3 AMP HUBBELL USB CHARGER RECEPTACLE                     | 125V 15 AMP QUAD-USB 5VDC 3 AMP HUBBELL USB CHARGER RECEPTACLE                       |
| 125V 15 AMP QUAD-USB 5VDC 3 AMP HUBBELL USB CHARGER RECEPTACLE                       | JUNCTION BOX   |
| JUNCTION BOX   | GENERATOR BATTERY CHARGER  |
| GENERATOR BATTERY CHARGER  | 2-BUTTON PUSH BUTTON STATION   |
| 2-BUTTON PUSH BUTTON STATION   | COAX-CABLE CONNECTION FOR TELEVISION   |
| COAX-CABLE CONNECTION FOR TELEVISION   | WALL MOUNTED DATA OUTLET   |
| WALL MOUNTED DATA OUTLET   | FLOOR DATA OUTLET  |
| FLOOR DATA OUTLET  | POWER DISCONNECT   |
| POWER DISCONNECT   | WATER HEATER ON DECK OR MEZZANINE ABOVE - SIZE AS NOTED ON PLAN                      |
| WATER HEATER ON DECK OR MEZZANINE ABOVE - SIZE AS NOTED ON PLAN                      | EXHAUST FAN - SEE MECH.  |
| EXHAUST FAN - SEE MECH.  |  |

**NOTES**  
1. VERIFY ALL EMERGENCY/EVAC LIGHT FIXTURES TO NEAREST CONSTANT POWER SOURCE

**DAMMON ENGINEERING, INC.**  
LOUISIANA & MISSISSIPPI

Chief Engineer: Brian Mistich, PE  
554 Old Spanish Trail  
Sulder, LA 70458

www.dammonengineering.com  
info@dammonengineering.com  
PH: 985.649.5832 F: 985.641.5950

#	DESCRIPTION	DATE

**GRACE WELLSHIP**  
34442 WILLIS ALLEY  
PEARL RIVER LA.

JOB No: 2340 DATE: 04/20/2018  
DRAWN BY: CKD CHECKED BY: BAM

SHEET TITLE:  
POWER PLAN  
PHASE A

DRAWING NUMBER:  
**E101**

13 of 13