

Luminaire Schedule						
Symbol	Qty	Label	Lumens	LLF	Description	Filename
•	106	XP	2850	0.660	XP2GVA432120D4	XP2GVA432.IES
⊙	159	R1	2400	0.750	1146	1146-32W.IES
⊕	1	RA1	4889	0.750		45677.ies
⊖	3	W	900	0.750	408877 _ 40885U	408877.IES

Numeric Summary									
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min		
Reception_Floor-WP	Illuminance	Fc	23.22	28.9	17.3	1.34	1.67		
Fitness Room_Floor-WP	Illuminance	Fc	88.64	125	21.9	4.05	5.70		
Break Room_Floor-WP	Illuminance	Fc	110.19	137	77.5	1.42	1.77		
WC 1_Floor-WP	Illuminance	Fc	64.09	74.7	57.2	1.12	1.31		
WC 2_Floor-WP	Illuminance	Fc	57.71	64.8	50.3	1.15	1.29		
Staff Locker_Floor-WP	Illuminance	Fc	64.82	76.4	46.0	1.41	1.66		
Dry Storage_Floor-WP	Illuminance	Fc	83.39	101	57.0	1.46	1.78		
Kitchen_Floor-WP	Illuminance	Fc	82.19	133	0.1	821.90	1328		
Ceafs Office_Floor-WP	Illuminance	Fc	51.83	62.7	39.5	1.31	1.59		
Furniture Storage_Floor-W	Illuminance	Fc	93.56	133	42.9	2.18	3.09		
Paper Storage_Floor-WP	Illuminance	Fc	90.49	110	60.1	1.51	1.83		
Banquet Service_Floor-WP	Illuminance	Fc	64.05	102	3.6	17.79	28.44		
Ladies Room_Floor-WP	Illuminance	Fc	16.17	30.7	0.1	161.70	307.00		
Ladies Restroom 1_Floor-W	Illuminance	Fc	21.06	29.7	9.0	2.34	3.30		
Ladies Lounge_Floor-WP	Illuminance	Fc	19.47	28.9	8.3	2.35	3.48		
Corridor 1_Floor-WP	Illuminance	Fc	18.28	22.1	15.3	1.19	1.44		
Mens Restroom_Floor-WP	Illuminance	Fc	22.55	34.2	12.4	1.82	2.76		
Manager_Floor-WP	Illuminance	Fc	95.53	113	70.9	1.35	1.59		
Hall_Floor-WP	Illuminance	Fc	20.23	21.5	18.7	1.08	1.15		
Assit Manager_Floor-WP	Illuminance	Fc	71.08	93.2	51.6	1.38	1.81		
Office 2_Floor-WP	Illuminance	Fc	82.70	107	52.9	1.56	2.01		
Corridor 2_Floor-WP	Illuminance	Fc	8.72	13.8	5.3	1.65	2.60		
Lounge_Floor-WP	Illuminance	Fc	11.83	18.5	4.7	2.52	3.94		
Room_9_Floor-WP	Illuminance	Fc	13.16	16.8	6.7	1.96	2.51		
Corridor 3_Floor-WP	Illuminance	Fc	11.22	15.2	7.2	1.56	2.11		
Corridor 4_Floor-WP	Illuminance	Fc	12.05	15.9	8.0	1.51	1.99		
Corridor 5_Floor-WP	Illuminance	Fc	10.78	14.8	6.3	1.71	2.35		
Side Entery 3_Floor-WP	Illuminance	Fc	6.27	15.2	0.2	31.35	76.00		
Pro_Floor-WP	Illuminance	Fc	72.73	91.3	49.9	1.46	1.83		
Golf Shop_Floor-WP	Illuminance	Fc	15.35	25.9	2.7	5.69	9.59		
Grill Prep_Floor-WP	Illuminance	Fc	89.75	130	37.7	2.38	3.44		
Grill Bar_Floor-WP	Illuminance	Fc	92.75	131	56.4	1.64	2.33		
Mens Locker_Floor-WP	Illuminance	Fc	21.60	31.1	10.0	2.16	3.11		
Bar Storage_Floor-WP	Illuminance	Fc	85.33	98.1	75.7	1.13	1.30		
Banquet_Floor-WP	Illuminance	Fc	14.48	19.1	6.0	2.41	3.18		
Vestibule 1_Floor-WP	Illuminance	Fc	35.31	214	9.4	3.76	22.78		
Room_7_Floor-WP	Illuminance	Fc	9.98	16.8	0.4	24.95	42.00		
Bus Station_Floor-WP	Illuminance	Fc	21.35	26.1	17.8	1.20	1.47		
Ladies Card_Floor-WP	Illuminance	Fc	10.18	17.1	4.1	2.48	4.17		
Mens Grill_Floor-WP	Illuminance	Fc	13.70	18.7	7.3	1.88	2.56		
Office 1_Floor-WP	Illuminance	Fc	71.14	88.0	53.8	1.32	1.64		
Foyer_Floor-WP	Illuminance	Fc	21.16	28.9	12.4	1.71	2.33		

57.7 94.7 54.4 XP 91.2 95

59.8 56.2 57.2 92.2 92

50.3 50.7 92.1 91.

53.3 54.0 52.0 52.5 57.2 57

Acknowledgement/Disclaimer

By receipt of this document in paper form or electronic version via email, the recipient(s) shall read this document thoroughly, accept the following as an integral part of the photometry files provided herein. Printed versions of these photometry files shall include the below disclaimer language:

File Name: Tchefuncta Country Club fc.dwg  
Date: 02/28/07  
Calculations have been performed according to IESNA & CIE standards and good practice. Some differences between measured values and calculated results may occur due to tolerances in the calculation methods, testing procedures, component performance, measured techniques and field conditions such as voltage and temperature variations. Input data used to generate the attached calculations such as room dimensions, reflectances, furniture and architectural elements significantly affect the lighting calculations. If the real environmental conditions do not match the input data, and actual lamps installed, differences will occur between values and calculated results.