

TABLE INSET:

(1) Archery, Golf Driving, Shooting, similar ranges; and Miniature Golf, and other similar activities	1 1/2 spaces for each station, tee, or 2 holes.
(2) Automobile Repair Garage	One (1) space for each employee.
(3) Boarding and Lodging Houses	One (1) space for each bedroom plus one (1) additional space for resident manager.
(4) Bowling Alleys	Five (5) spaces per alley.
(5) Batting Cages	Outdoor: Two (2) spaces per station Indoor: One (1) space for each two hundred (200) square feet of gross floor area.
(6) Business and Professional Offices	One (1) space for each three hundred (300) square feet of gross floor area.
(7) Child Care Center	Four (4) spaces plus one (1) space per five hundred (500) feet of gross floor area.
(8) Churches, Temples and other places of worship	One (1) space for each ten (10) seats in main auditorium.
(9) Clinics	One (1) space for each four hundred (400) square feet of gross floor area.
(10) Clubs and Lodges	One (1) space for each three (3) members plus one (1) space for each sixty (60) square feet of gross floor area that is available to the general public.
(11) Commercial Amusement activities	One (1) space for each two hundred (200) square feet of gross floor area.
(12) Commercial Manufacturing and Industrial Establishments not catering to Retail Trade	One (1) space for each three (3) employees on the largest work shift plus one (1) space for each company vehicle operating from the premises.
(13) Dance Halls, Exhibition Halls, Bingo Halls and Places and Gymnasiums	One (1) space for each sixty (60) square feet of gross floor area.
(14) Dwellings - Single-family Two-family Three- and Four-Family Multiple-family	One (1) space per dwelling unit One (1) space per dwelling unit, One and one-half (1.5) spaces per dwelling unit, One and one-half (1.5) spaces per dwelling unit. For multiple-family dwellings or condominiums that exceed the maximum height allowed by right, the following requirements apply: 1.5 spaces per dwelling unit for efficiency and 1-bedroom; and 2.0 spaces per dwelling unit for 2 or more bedrooms
(15) Elderly Housing	One (1) space for each two (2) Assisted Living Facility dwelling units plus one (1) additional space for each four (4) employees on the largest shift. Parking for any use other than allowed under the definition of Assisted Living Facility as stated in section 40-3, Definitions of this ordinance, shall be determined in accordance with the requirements for the individual use and shall be

and Assisted Living Facility	computed separately. Elderly Housing - One (1) space for each dwelling unit plus one (1) additional space for each four (4) employees on the largest shift. Parking for any use other than allowed under the definition of Elderly Housing as stated in section 40-3, Definitions of this ordinance, shall be determined in accordance with the requirements for the individual use and shall be computed separately.
X (16) Furniture Store, Appliance Center and Computer Stores	One (1) parking space for every three (3) employees plus one (1) parking space for each six hundred (600) square feet of gross floor area.
(17) Casino, Gaming Establishments and/or Gaming related activities and accessory uses	1. One (1) parking space for each fifty (50) square feet of gaming area, plus one (1) space for each employee at the maximum shift.
	2. Bus parking shall be provided at a rate of one and one-half (1.5) percent of the above required parking spaces. The minimum bus parking space shall be a minimum of twelve (12) feet in width and forty-five (45) feet in length exclusive of access or maneuvering area, ramps and other appurtenances.
	3. On-site accessory uses or structures shall provide off-street parking in accordance with the requirements otherwise listed in Article XXXV. Off-Street Parking and Loading Regulations.
→ (18) General Business, Commercial or Personal Service Establishments, catering to retail trade, including "Supermarkets"	One (1) space for each two hundred (200) square feet of gross floor area
(19) Home Occupations	One (1) space in addition to the parking space(s) required for the residential use
(20) Hospitals	One (1) space for each four (4) beds plus one (1) space for each staff doctor plus one (1) space for each four (4) employees including nurses.
(21) Hotel, Transient	1 space per guestroom; plus 1 space for every 200 square feet of gross floor area used for restaurants and lounges; plus 1 space for every 200 square feet of gross floor area used for convention facilities, meeting rooms, banquet halls, or similar uses.
(22) Kennels and Animal Hospital	One (1) space for each four hundred (400) square feet of gross floor area
(23) Kindergartens, Family Day Care Homes, Nursery Schools or Pre-Schools	One (1) space for each ten (10) children
(24) Libraries and Museums	One (1) space for each four hundred (400) square feet of gross floor area
(25) Mini-Storage Structure	One (1) space for each three thousand (3,000) square feet of storage area or one (1) space per one hundred (100) storage units, whichever is greater.
(26) Motels and Tourist Homes	One (1) space for each guest bedroom plus one (1) additional space for resident manager

(27) Nursing and Convalescent Homes and Institutions	One (1) space for each eight (8) beds
(28) Printing Establishment	One (1) space for each employee plus one (1) space for each company vehicle operating from the premises
(29) Restaurants and Lounges	One (1) space for each one hundred fifty (150) square feet of gross floor area
(30) Riding Stables	One (1) space for each four hundred (400) square feet of covered area of such stable
(31) Roadside Stands	Five (5) spaces for each such establishment
(32) Schools, Dancing and Music	One (1) space for each ten (10) pupils or students
(33) Schools, Public and Private	Elementary and junior high schools, two (2) spaces per classroom, laboratory or manual training shop. High schools, eight (8) spaces per classroom, laboratory or manual training shop. Colleges, universities, trade, industrial and business schools, ten (10) spaces per classroom, laboratory or other teaching room
(34) Schools having Auditoriums, Gymnasiums, or Sports Arenas	Schools with such facilities shall have parking that accommodates the highest number of parking spaces required when the required parking spaces for the school and each such facility are calculated; i.e., the use requiring the highest number of parking spaces shall be the parking requirement that applies.
(35) Skating Rink	One (1) space for each one hundred fifty (150) square feet of gross floor area
(36) Theaters, Auditorium, Sports Arenas and Places of Public Assembly	One (1) space for each three (3) seats or twenty (20) spaces per athletic field without seating. Multipurpose athletic fields without parking shall provide parking for all possible field arrangements; e.g., one (1) football-sized field that will also be used for two (2) baseball diamonds shall provide parking for two athletic fields.
(37) Townhouses	One (1) space for each dwelling unit