



FLOOR PLAN NOTES:

- DO NOT SCALE DRAWINGS. USE ONLY DIMENSIONS SHOWN ON DRAWINGS. IF DIMENSIONS ARE IN QUESTION, THE BUILDER SHALL BE RESPONSIBLE FOR OBTAINING DIMENSIONS FROM THE ARCHITECT AND VERIFYING DIMENSIONS AND CONDITIONS AT JOB SITE.
- BUILDER SHALL ESTABLISH FINISH FLOOR ELEVATIONS AS SHOWN IN DRAWINGS. BUILDER SHALL TAKE INTO ACCOUNT DESIGN INTENT, INCLUDING NUMBER OF STEPS, WATER TABLE MASONRY, ETC. BUILDER SHALL ALSO ASSURE THAT THERE IS ADEQUATE CLEARANCE BETWEEN FINISH GRADE AND ANY WOOD CONSTRUCTION. WINDOW SIZES INDICATED ON PLANS ARE GENERIC SASH SIZES.
- WALLS, CEILINGS, AND FLOORS OF ANGLIARY SPACES SUCH AS CLOSET'S AND STORAGE AREAS SHALL MATCH THE ROOMS THEY SERVE UNLESS NOTED OTHERWISE.
- COORDINATE LOCATIONS OF UTILITY METERS ON PLANS TO BE AWAY FROM PUBLIC VIEW AND MINIMIZE VISUAL IMPACT FROM ANY OTHER AREAS OF THE SITE. HOLD METERS AS LOW AS POSSIBLE TO ALLOW MORE EFFECTIVE SCREENING.
- SPRINKLE POWDERED BORIC ACID INTO BOTTOM TRACK AT A RATE OF 1/4 CUP PER 2' OR PLATE IN WALLS ADJACENT TO KITCHEN, BATH, OR OTHER WET OR HIGH TRAFFIC AREAS. BURN IN SPREAD IMMEDIATELY BEFORE INSULATION IS INSTALLED IN INSULATED WALLS OR MEDIUMFIELD BEFORE INSTALLATION OF SHEETROCK ON UN-INSULATED WALLS.
- MOISTURE RESISTANT GYPSUM BOARD SHALL BE USED THROUGHOUT RESTROOMS. OWNER.
- BUILDER SHALL COORDINATE ALL SHELVING AND STORAGE REQUIREMENTS WITH OWNER.
- CENTER PLUMBING FIXTURES IN SPACE PROVIDED UNLESS OTHERWISE NOTED. PROVIDE NOT LESS THAN THE FOLLOWING CLEARANCES FROM FINISHED WALL TO FIXTURES ON EITHER SIDE: LAVATORY = 15", TOILET = 18".

WINDOW SCHEDULE				REMARKS
TYPE	FRAME	GLASS	LITES	ACCESS.
◆	FIXED	VERT. SLIDE		
◇	HORIZ. SLIDE			
○	CIRCLEHEAD			
●	STEEL			
●	ALUMINUM			
●	WOOD			
■	TINTED			
□	PLAN			
■	INSULATED			
■	MILD GLASS			
■	2/2			
■	15 LITES			
■	9 LITES			
■	NONE			
■	SCREEN			
■	SHUTTER			
■	NONE			
■	ALARM			
				MAX. U-FACTOR
				.75

DOOR & HARDWARE SCHEDULE				REMARKS
TYPE	FRAME	HINGE	LOOK	ACCESSORIES
⊙	CLAD/GLASS			
⊙	HOLLOW METAL			
⊙	WOOD SOLID CORE			
⊙	STEEL			
⊙	WOOD			
⊙	ALUMINUM			
⊙	CASED OPENING			
⊙	OIL SWING			
⊙	BUT			
⊙	BURGLERPRF			
⊙	PASSAGE			
⊙	PRIVACY			
⊙	KEYED HANDLE			
⊙	PANIC			
⊙	THRESHOLD			
⊙	WEATHERSTRIP			
⊙	DOOR STOP			
				EXTERIOR
				INTERIOR
				BATHROOM
				STALL DOORS

FLOOR PLAN
SCALE: 1/4" = 1'-0"

FLOOR PLAN

NEW BUILDING - STORE
-
SLIDELL, LOUISIANA

SLIDELL KOA CAMPGROUND

DAMMON ENGINEERING, INC.

1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458
DAMMONENGINEERING.COM

SCALE: AS NOTED

FILE:

JOB NO.

DATE:

SHEET

A-1

OF