


CR14 – Four-Post Lift



Description



Accessories



Specifications



Request More Info

Specifications

Specifications	CR14N201Y	Differences	CR14N202Y
Capacity	14,000 lbs. (6350kg)		14,000 lbs. (6350kg)
Rise	78-3/4" (2000mm)		78-3/4" (2000mm)
Maximum Wheelbase	182-1/2" (4635mm)	<32-1/2 ">	215" (5460mm)
Overall Length	250" (6350mm)	<33 ">	283" (7188mm)
Overall Width	131-3/4" (3568mm)		131-3/4" (3568mm)
Width Inside Columns	116-1/4" (2953mm)		116-1/4" (2953mm)
Length Between Columns	195-1/4" (4946mm)	<33 ">	228-1/4" (4946mm)
Overall Height	90-1/2" (2299mm)		90-1/2" (2299mm)
Runway Width	20" (508mm)		20" (508mm)
Runway Height	7" (178mm)		7" (178mm)
Width Between Runways	43" (1092mm) or 46" (1168mm)		43" (1092mm) or 46" (1168mm)
Rise Time	72 seconds		72 seconds
Voltage*	208/230v		208/230v
Motor	2HP		2HP
Minimum Bay Size	15' x 25' (4572 x 7620mm)	<36 ">	15' x 28' (4572 x 8534mm)
* single phase standard; 3-phase available at additional cost Specifications subject to change without notice or liability			