



- PLAN NOTES: UNLESS NOTED OTHERWISE:
- TOP OF SLAB EL. 0'-0".
 - EXISTING CONCRETE Waffle Joist Floor System (14'-3" CONCRETE SLAB+17" TOTAL THICKNESS).
 - (E) - INDICATES EXISTING CONSTRUCTION.
 - (N) - INDICATES NEW CONSTRUCTION.
 - (N) - INDICATES NEW IN-FILL SLAB TO CONSIST OF 3" THICK CONCRETE SLAB THROUGHOUT (f=4,000PSI, NORMAL WEIGHT). TOP OF SLAB EL. TO MATCH EXISTING. COORD. WITH EXIST. FINISHES.
 - (N) - INDICATES NEW SLAB/BEAM EXTENSION TO NEW B/L - SEE SECTIONS (f=4,000PSI, NORMAL WEIGHT). TOP OF SLAB EL. TO MATCH EXISTING. COORD. WITH EXIST. FINISHES.
 - (N) - INDICATES BUILT UP FLOOR SYSTEM ON TOP OF CONCRETE ON METAL DECK TO CONSIST OF 3" CONCRETE SLAB ON RIGID STYROFOAM BOARD FILL, REIN. SLAB W/ #6-W/4M14 W.W.F. LOCATED AT MID-DEPTH OF SLAB.
 - (N) - INDICATES 5" THICK CONCRETE SLAB THROUGHOUT (NORMAL WEIGHT, f=4,000 PSI). PROVIDE #3@12" TEMPERATURE REINFORCING. PLACE ON TOP OF AND PERP. TO MAIN SLAB REIN. TYPICAL. SEE SECTIONS FOR MAIN SLAB REIN.
 - (N) - INDICATES SINGLE 14"x14" PRECAST PILE. SEE SECTIONS FOR CUT-OFF.
 - (N) - INDICATES X-BRACING. SEE 2/S2-7.
 - (N) - INDICATES K-BRACING. SEE 3/S2-7.
 - (N) - INDICATES 8" OR 12" CMU WALLS. SEE 4/S2-7.

1 100 LEVEL FRAMING PLAN
1/8"=1'-0"

PRELIMINARY
NOT FOR CONSTRUCTION

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

MORPHY CONSULTING ENGINEERS
336 N. Jeff Davis Pkwy.
New Orleans, LA 70119
TEL: (504) 488-1317
FAX: (504) 488-9924
WEB: www.mmi-eng.com
INCORPORATED JOB NO. 10128

Holabird & Root / Holly & Smith LLC expressly disclaims any responsibility arising from any unauthorized use of these plans, drawings and notes. Any authorization must be in writing.
This drawing copy may have been reproduced at a size different than originally drawn. The Owner and Architect assume no responsibility for use of incorrect scale. Drawings are not to be scaled.
Not published - All rights reserved.

HOLABIRD & ROOT | **HOLLY & SMITH LLC**
140 South Dearborn Avenue Suite 500 Chicago, IL 60660
541 Julia Street Suite 201 New Orleans, LA 70130
312.357.1771 (tel) 312.357.1909 (fax) www.holabird.com
504.585.1315 (tel) 504.585.1316 (fax) www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

LOYOLA UNIVERSITY NEW ORLEANS
Monroe Hall Renovation

100 LEVEL FRAMING PLAN
Sheet Name
Drawing No. S2-1