



GA FILE NO. WP 1072 GENERIC

ONE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR GYPSUM VENEER BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE OF 3-5/8" STEEL STUDS 24" O.C. WITH 1" TYPE S DRYWALL SCREWS 8" O.C. AT VERTICAL JOINTS AND 12" O.C. AT FLOOR AND CEILING RUNNERS AND INTERMEDIATE STUDS.
 JOINTS STAGGERED 24" ON EACH SIDE AND ON OPPOSITE SIDES.
 SOUND TESTED WITH 3-1/2" GLASS FIBER FRICTION FIT IN STUD SPACE. (NON-LOAD BEARING)



FLOOR PLAN
 SCALE: 3/16" = 1"

NOTE: ALL DIMENSIONS ARE TO FACE OF G.F. DD EXCEPT COLUMN GRID LINES, UNLESS OTHERWISE NOTED.

REVISIONS		DATE
#	DESCRIPTION	

GREEN-STATEFARM RETAIL COMPLEX-TENANT BUILDOUT
 381-391 CALISE BOULEVARD, WEST
 SUDELL, LOUISIANA

JOB No: DATE: 12-11-2012
 DRAWN BY: JTL CHECKED BY:

DAMMON ENGINEERING INC.
Architects & Engineers

Chief Engineer: EMMETT DAMMON, P.E.
 Chief Architect: ROBERT WILTSE
 554 OLD SPANISH TRAIL
 SUDELL, LA 70450

dammoneg@bellsouth.net
 PHONE: 985-649-5032
 FAX: 985-641-5950

REVISED LATEST FLOOR PLAN SCHEME - C

A-1