



**PLOT PLAN SYMBOL SCHEDULE**

- 2" C. STUB OUT AND CAP 18" BEYOND FIN. WALKWAY MIN. 18" BELOW GRADE ENCASE IN CONCRETE, MIN. 3" ALL AROUND. (TELEPHONE). TRENCHING AND BACKFILL FOR BURIED TELEPHONE CABLES BY ELEC. CONTRACTOR. SHOVEL WIDTH X 18" DEEP.
- T- TELEPHONE CONDUIT MIN. 18" BELOW GRADE ENCASED IN CONCRETE MIN. 3" ALL AROUND. SIZE AS NOTED
- E- UNDERGROUND FEEDER 480V. MIN. 24" BELOW GRADE, MIN. 3" CONCRETE ALL AROUND.
- L- UNDERGROUND FEEDER 120/208V. MIN. 24" BELOW GRADE, MIN. 3" CONCRETE ALL AROUND.
- E- EMERGENCY FEEDER MIN. 24" BELOW GRADE, MIN. 3" CONCRETE ALL AROUND.

WESTWEGO  
AVE.