



DEMOLITION NOTES - PARKING LOT

- ① REMOVE EXISTING CONCRETE CURBS AND PLANTER AREAS.
- ② REMOVE ALL ASPHALT IN PARKING LOT.
- ③ PREPARE DITCHES FOR FILL AND INSTALLATION OF NEW CULVERT PIPES.
- ④ REMOVE LEANING TREES AND CLEAN OUT VEGETATION.
- ⑤ REMOVE EXISTING POWER POLE.
- ⑥ PREPARE EXISTING FIBER OPTIC POLE FOR MOVE.
- ⑦ REMOVE EXISTING 15" RCP.
- ⑧ REMOVE TREES, UNDERBRUSH & TOPSOIL.
- ⑨ PREPARE FOR CONSTRUCTION OF NEW PARKING LOT.
- ⑩ REMOVE TREES AND GRASS. PREPARE AREA FOR REPLANTING.
- ⑪ REMOVE EXISTING MONUMENT.
- ⑫ DEMO EXISTING CONCRETE PAD. SEE DWG. C-3 FOR DETAILS

NOTE:
 SEE DWG. C-3 FOR NEW SITE PLAN LAYOUT.
 SEE DWG. C-4 FOR NEW PAVING AND DRAINAGE PLAN.
 SEE DWG. L-1 FOR NEW LANDSCAPING PLAN.

PARKING LOT DEMOLITION PLAN
 SCALE: 1"=20'-0"

CONTRACT SET- 10/10/07

OF	D-9
SHEET	
DATE: 1-8-07	
JOB NO. 1729	
FILE:	
SCALE: 1"=20'	

RENOVATE OFFICE BUILDING

DAMMON ENGINEERING, INC.

1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458
 DAMMONENGINEERING.COM

PARKING LOT DEMO PLAN

ST. TAMMANY PARISH OFFICE BUILDING
 520 OLD SPANISH TRAIL
 SLIDELL, LOUISIANA