


FIRST FLOOR STRUCTURAL PLAN
 SCALE: 1/8" = 1'-0"
 NEW COLUMNS, BEAMS & ROOF - SEE SHIT. A-1

- NOTES:**
- ELEVATOR CONTRACTOR SHALL RELOCATE 1ST FLOOR STOPS TO ACCOUNT FOR RAISING FLOOR 3".
 - INSTALL 4" SCHEDULE 40 PIPE COLUMN W/ 6" X 8" X 1/2" PLATE T & B @ FLOORS 1 THRU 6 TO SUPPORT EXISTING HORIZONTAL WF BEAM PRESENTLY ATTACHED TO VERTICAL COLUMN AT EXTERIOR OF WALL. WELD NEW COLUMN TO BOTTOM OF EXISTING BEAM ABOVE. REMOVE EXTERIOR COLUMN, TRIM BEAM TO WALL AND ADD NEW SIDING TO MATCH, PATCH INTERIOR WALL (4 LAYERS OF 5/8" GYPSUM W/ GYP. BOARD).
 - ALL MISC. STEEL SHALL BE ASTM A36.

LEGEND
 NEW WALLS - [Hatched Pattern]
 NEW BRICK VENEER WALL - [Dashed Pattern]

CLOSE THE OPENING WITH LIGHT GAUGE METAL FRAME AND SHEATHING TO MATCH EXISTING ELEVATOR TOWER

16" LONG X 6" HIGH LOUVERED AND SCREENED OPENING IN EXISTING CMU WALL AT FLOOR LEVEL (8 TYPICAL)



= ADDENDUM 7 CHANGE

ADDENDUM 7 REVISED: 08/20/07
 REVISED: 05/21/07
 REVISED: 03/07/07

CONTRACT SET - 10/10/07

SHEET S-1 OF	SCALE: AS NOTED	JOB NO. 1729	DATE: 1-8-07	FILE:	DAMMON ENGINEERING, INC. 1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458 DAMMONENGINEERING.COM	RENOVATE OFFICE BUILDING	1ST FLOOR STRUCTURAL PLAN
	ST. TAMMANY PARISH ADMIN. COMPLEX 520 OLD SPANISH TRAIL SLIDELL, LOUISIANA						