



EXHAUST FAN SCHEDULE

NUMBER REQUIRED	LOCATION OF FAN	CFM REQUIRED	STATIC PRESSURE (INCHES WATER)	HORSEPOWER (OR EQUAL)	FAN TYPE
2	STAIR TOWER AIR SUPPLY	1,280	0.12	0.25	HARTZELL 12" A02SH1240--STAD03 277 V / 390 / 60hz / 0.25hp PROPELLER FAN
2	EXECUTIVE TOILETS EXHAUST	40	0.20	0.04	BROAN QTXE050 120 V / 180 / 60 Hz / 36 W
2	6th FLOOR TOILETS EXHAUST	570	0.25	0.47	BROAN LOSONE L700L 120 V / 180 / 60 Hz / 31.3 W
2	5th FLOOR TOILETS EXHAUST	475	0.25	0.35	BROAN LOSONE L500L 120 V / 180 / 60 Hz / 23.2 W
2	4th FLOOR TOILETS EXHAUST	515	0.25	0.47	BROAN LOSONE L700L 120 V / 180 / 60 Hz / 31.3 W
2	3rd FLOOR TOILETS EXHAUST	425	0.25	0.35	BROAN LOSONE L500L 120 V / 180 / 60 Hz / 23.2 W
2	2nd FLOOR TOILETS EXHAUST	465	0.25	0.35	BROAN LOSONE L500L 120 V / 180 / 60 Hz / 23.2 W
2	1st FLOOR TOILETS EXHAUST	250	0.25	0.34	BROAN LOSONE L250L 120 V / 180 / 60 Hz / 25.2 W

SCALE: AS NOTED

SEE VAN UNITS W/ EDH SPACE CONDITIONS: 75°F, 50% RH

** 2 SPD, 1750/1150 RPM MOTOR

*** 2 SPD, 1750/850 RPM MOTOR

REVISIONS

NO.	DATE	DESCRIPTION
REVISD	10-10-07	ab
REVISD	05-10-07	ab
REVISD	05-02-07	ab
REVISD	04-09-07	ab
REVISD	03-01-07	dd

CONTRACT SET - 10/10/07

NOTE:
PROVIDE ANTI-FREEZE PROTECTION SOLUTION FOR 20°F AMBIENT TEMPERATURE.

DAMMON ENGINEERING, INC.
1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458
DAMMONENGINEERING.COM

RENOVATE OFFICE BUILDING

HVAC SYSTEM SCHEDULES & DETAILS
ST. TAMMANY PARISH ADMIN. COMPLEX
520 OLD SPANISH TRAIL
SLIDELL, LOUISIANA

FILE: _____
JOB NO. 1729
DATE: 1-8-07
SHEET M-8 OF