



LIGHTING SCHEDULE

SYM	QTY	MARK	MFG	PART NUMBER	DESCRIPTION	HEIGHT
	9	F1	ELITE	8-OEC-LED-14000L/16000L/1800OLDIM10-MVOLT-35K/40K/50K-85	8' LED STRIP SELECTABLE	
	52	F2	ELITE	HH6-LED-1200L-DIM10-MVOLT-3OK-MD-90/HH6-6501-CL-MH	6" LED DOWNLIGHT 1200LUMENS 90CRI 30K	9' AFF
	4	F3	ELITE	4-OEC-LED-5000L-DIM10-MVOLT-40K-85	4' LED STRIP 5000L 40K	9' AFF
	3	F4	ELITE	ECH-BL-LED-1003-3	24" VANITY LED LIGHT	9' AFF
	6	F5	ELITE	ECH-PL-1025	12" PENDANT	
	4	F6	LIGHT ALARMS	CAMACSDDB-CMP	LED EXT WALL LIGHT - EGRESS	9' AFF
	6	F1	ORION LIGHTING	LSMF1-A1(3000LUMENS)-UNV-FD-8CS(30K)XX-BB-SP	LED WALLPACK 3000 LUMENS 30K BATTERY BACKUP	7' AFF
	2	F8	ALUMILITE	AR14-12/LED-UV-30K-XX-PG-SS-CCA	14" RLM 12M LED STRAIGHT SHROUD 30K PRISMATIC GLASS MET	14'
	1	F9	ALUMILITE	AR14-12/LED-UV-30K-XX-PG-5CA	14" RLM 12M LED ANGLED SHROUD 30K PRISMATIC GLASS MET	17'
	3	CF1	MINKA AIRE	MINKA AIRE F546-B5	42" 5 BLADE INDOOR CEILING FAN	
	1	CF2	BIG ASS FANS	BIG ASS FAN POWERFOIL 8-08	8' DIAMETER INDUSTRIAL FAN	
	7	EX	ELITE	ELX-603-R-M	LED EXT	
	9	EM	ELITE	ELM-LED-803-M	LED EMG LIGHT W/BATTERY BACKUP	
	2	S1	ORION LIGHTING	IAHP1-A1-UNV-FD-730-XX-T4-T52-SP	AREA LIGHT TYPE IV 30K, 76W 13000 LUMENS ON 16' SQUARE STRAIGHT STEEL POLE. SEE SIGHT PLAN FOR PLACEMENT	

1. DIMMER. DIMMABLE LIGHTS, LUT ARE GANGED. SHALL ALSO FLUORESCENCE BE LUTRON
2. WHERE TO BE DIMMABLE. DIMMING TO BE COMPATIBLE WITH THE FI
3. ALL EM HAVE 90 M TEST BUTTC
4. ALL FLI DOUBLE-EN SHALL BE F MEANS IN A
5. PROVIDE DETECTION INSTALL ALL OF THE STP DISTRICT.

1 PRO HOT MINUS

Light

\$ LIGHT SWIT
 \$R RHE LIGT
 \$3 3-W SWIT
 S SMC DET