

SECTION 123530
RESIDENTIAL CASEWORK

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes kitchen cabinets.

1.2 DEFINITIONS

- A. MDF: Medium-density fiberboard.

1.3 ACTION SUBMITTALS

- A. Product Data: For the following:
1. Cabinets.
 2. Cabinet hardware.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Certificates: For casework.

PART 2 - PRODUCTS

2.1 CABINETS

- A. Basis of Design: Subject to compliance with requirements, provide product indicated on Drawings or comparable product by one of the following:
- Cabinetry by Diamond
 - Aristokraft Cabinetry
 - Singer Kitchens
- B. Product Line: Prelude
Door Style: Wallace

2.2 CABINET MATERIALS

A. General:

1. Adhesives and Composite Wood and Agrifiber Products: Do not use products that contain urea formaldehyde.
2. Hardwood Lumber: Kiln dried to 7 percent moisture content.
3. Softwood Lumber: Kiln dried to 10 percent moisture content.
4. Hardwood Plywood: HPVA HP-1; made with adhesive containing no urea formaldehyde.
5. Particleboard: ANSI A208.1, Grade M-2; made with binder containing no urea formaldehyde.
6. MDF: ANSI A208.2, Grade MD; made with binder containing no urea formaldehyde.

B. Exposed Materials:

1. Exposed Wood Species: Maple
 - a. Select materials for compatible color and grain. Do not use two adjacent exposed surfaces that are noticeably dissimilar in color, grain, figure, or natural character markings.
 - b. Staining and Finish: As selected by Architect from manufacturer's full range.
2. Solid Wood: Clear hardwood lumber of species indicated, free of defects.
3. Plywood: Hardwood plywood with face veneer of species indicated, with Grade A faces and Grade C backs of same species as faces.
4. Plastic Laminate: Particleboard faced with high-pressure decorative laminate complying with NEMA LD 3.
 - a. Colors, Textures, and Patterns: As selected by Architect from cabinet manufacturer's full range.

C. Concealed Materials: Solid wood or plywood, of any hardwood or softwood species, with no defects affecting strength or utility; particleboard; MDF; or hardboard.

2.3 CABINET HARDWARE

- A. General: Manufacturer's standard units complying with BHMA A156.9, of type, size, style, material, and finish as indicated by manufacturer's designations.
- B. Pulls: Back-mounted decorative pulls. Basis of design: Diamond Pull H63.
- C. Hinges: Concealed European-style, self-closing hinges.

- D. Drawer Guides: Epoxy-coated-metal, self-closing drawer guides; designed to prevent rebound when drawers are closed; with nylon-tired, ball-bearing rollers; and complying with BHMA A156.9, Type B05011 or Type B05091.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install cabinets with no variations in flushness of adjoining surfaces; use concealed shims. Where cabinets abut other finished work, scribe and cut for accurate fit. Provide filler strips, scribe strips, and moldings in finish to match cabinet face.
- B. Install cabinets without distortion so doors and drawers fit the openings, are aligned, and are uniformly spaced. Complete installation of hardware and accessories as indicated.
- C. Install cabinets level and plumb to a tolerance of 1/8 inch in 8 feet.
- D. Fasten cabinets to adjacent units and to backing.
 - 1. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches o.c. with No. 10 wafer-head screws sized for not less than 1-1/2-inch penetration into wood framing, blocking, or hanging strips.

3.2 ADJUSTING AND CLEANING

- A. Adjust cabinets and hardware so doors and drawers are centered in openings and operate smoothly without warp or bind. Lubricate operating hardware as recommended by manufacturer.

END OF SECTION 123530