

SECTION 104413  
FIRE PROTECTION CABINETS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes fire-protection cabinets for portable fire extinguishers.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For fire-protection cabinets.

1.3 COORDINATION

- A. Coordinate size of fire-protection cabinets to ensure that type and capacity of fire extinguishers indicated are accommodated.
- B. Coordinate sizes and locations of fire-protection cabinets with wall depths.

1.4 SEQUENCING

- A. Apply vinyl lettering on field-painted fire-protection cabinets after painting is complete.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Rated Fire-Protection Cabinets: Listed and labeled to comply with requirements in ASTM E 814 for fire-resistance rating of walls where they are installed.

2.2 FIRE-PROTECTION CABINET

- A. Cabinet Type: Suitable for fire extinguisher.
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated on Drawings Larsens Manufacturing Company, Occult Series or comparable product by one of the following:

- a. Fire-End & Croker Corporation.
  - b. GMR International Equipment Corporation.
  - c. Guardian Fire Equipment, Inc.
  - d. JL Industries, Inc.; a division of the Activar Construction Products Group.
  - e. Larsens Manufacturing Company.
  - f. Modern Metal Products, Division of Technico Inc.
  - g. Nystrom, Inc.
  - h. Potter Roemer LLC.
  - i. Strike First Corporation of America.
- B. Cabinet Construction: Nonrated.
- C. Cabinet Material: Cold-rolled steel sheet.
- D. Recessed Cabinet:
1. Trimless with Concealed Flange: Surface of surrounding wall finishes flush with exterior finished surface of cabinet frame and door, without overlapping trim attached to cabinet. Provide recessed flange, of same material as box, attached to box to act as drywall bead.
  2. Trimless with Hidden Flange: Flange of same metal and finish as box overlaps surrounding wall finish and is concealed from view by an overlapping door.
  3. Exposed Flat Trim: One-piece combination trim and perimeter door frame overlapping surrounding wall surface with exposed trim face and wall return at outer edge (backbend).
- E. Door Material: Stainless-steel sheet.
- F. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.
- G. Accessories:
1. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as directed by Architect.
    - a. Identify fire extinguisher in fire-protection cabinet with the words "FIRE EXTINGUISHER."
      - 1) Location: Applied to cabinet door.
      - 2) Application Process: Pressure-sensitive vinyl letters.
      - 3) Lettering Color: Black.
      - 4) Orientation: Vertical.
- H. Materials:
1. Cold-Rolled Steel: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B.
    - a. Finish: Baked enamel or powder coat.

- b. Color: As selected by Architect from full range of industry colors and color densities.
- 2. Stainless Steel: ASTM A 666, Type 304.
  - a. Finish: No. 4 directional satin finish.

## 2.3 FABRICATION

- A. Fire-Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Prepare recesses for recessed fire-protection cabinets as required by type and size of cabinet and trim style.
- B. Install fire-protection cabinets in locations and at mounting heights indicated or, if not indicated, at heights acceptable to authorities having jurisdiction.
- C. Fire-Protection Cabinets: Fasten cabinets to structure, square and plumb.
- D. Adjust fire-protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

END OF SECTION 104413