

FINISH SCHEDULE										
ROOM NAME	WALLS C3010 (NOTE 1)	STC REDD./PRVD.	EXTEND WALL TO DECK ABOVE	FLOOR C3020	WALL BASE C302008	CEILING C3030 (NOTE 1)	CABINETRY	NOTES	SQ. FT. REDD./PRVD.	COMMENTS
INTERIOR	EP/MPJ	NA	NO	CONC	RB	PS / MPJ	NA	(NOTE 1) (NOTE 2)	9207 / 8554	

- NOTES:  
1. PAINT ALL STRUCTURAL STEEL COLUMNS, BRACING AND OTHER STRUCTURAL MEMBERS UNLESS INDICATED OTHERWISE.  
2. "PAINTED STRUCTURE" INCLUDES ALL VERTICAL AND HORIZONTAL STRUCTURAL MEMBERS OCCURRING WITHIN THIS SPACE.

DOOR & HARDWARE SCHEDULE							
MARK	DETAILS HEAD JAMB SILL	SIZE	DOOR TYPE	FRAME	HINGE	LOCK	REMARKS
<b>EXTERIOR DOORS</b>							
1	12 A1.20	13 A1.20	14 A1.20	3/0 x 6/8	INSULATED HOLLOW METAL	STEEL HOLLOW METAL	BUTT 1-1/2 PR KEYS HANDLE DOOR STOP, SLINGER, CLOSER, KICK PLATES AT INTERIOR AND VISION LITE
2	26 A1.21	27 A1.21	28 A1.21	26/0 x 16/0	OVERHEAD DOOR		

WINDOW SCHEDULE							
MARK	DETAILS HEAD JAMB SILL	SIZE	DOOR / WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
A	23 A1.22	24 A1.22	25 A1.22	4/0 x 3/6	FIXED	ALUMINUM	TINTED, INSULATED, LOW-E

RECORD DRAWING  
LETTER DATED -  
5-27-10



			DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY - PRE-FINAL DOOR, WINDOW & FINISH SCHEDULES	DES. R. WILTSE    DRW. J. TIFANY PROJ. T. ARBIB CHECKED BY: R. WILTSE DATE: 5/27/10 SCALE: AS SHOWN SHEET NO. 56 OF 132	AS-BUILT REVISED AS PER URS COMMENTS 9 OCTOBER 2009 DATE: 4-25-10 DATE: 11-6-09 APPR: RW APPR: RW
--	--	--	---	--	--