

DOOR & HARDWARE SCHEDULE

MARK	DETAILS	SIZE	DOOR TYPE	FRAME	HWDR. NO.	STC	REMARKS
EXTERIOR DOORS							
1	(12) (13) (14) A1.20 A1.20 A1.20	PR. 3/0 x 7/0	ALUM. STOREFRONT	GLV. PTD. STEEL	-	NA	FULL GLAZED LITE GLAZING TO MATCH WINDOWS
2	(12) (17) (14) A1.20 A1.20 A1.20	PR. 3/0 x 7/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	4"x24" VISION LITE, GLAZING TO MATCH WINDOWS - RATED 1 HR.
3	(12) (13) (14) A1.20 A1.20 A1.20	PR. 2/10 x 7/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	
4	(12) (13) (14) A1.20 A1.20 A1.20	4/0 x 7/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	4"x24" VISION LITE, GLAZING TO MATCH WINDOWS
5	(12) (13) (14) A1.20 A1.20 A1.20	3/6 x 7/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	4"x24" VISION LITE, GLAZING TO MATCH WINDOWS, RATED
6	(12) (13) (14) A1.20 A1.20 A1.20	3/0 x 7/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	4"x24" VISION LITE, GLAZING TO MATCH WINDOWS
7	(26) (27) (28) A1.21 A1.21 A1.21	26/0 x 16/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	OVERHEAD DOOR
8	(26) (27) (28) A1.21 A1.21 A1.21	12/0 x 16/0	GLV. PTD. STEEL INSUL.	GLV. PTD. STEEL	-	NA	OVERHEAD DOOR
INTERIOR DOORS							
9	(18) (19) (-) A1.21 A1.21 (-)	PR. 3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	50	
10	(-) (-) (-) (-) (-) (-)	5/0 x 6/8	HOL. METAL CASED OPENING	PTD. STEEL	-	NA	
11	(-) (-) (-) (-) (-) (-)	4/0 x 7/4	OMU CASED OPENING	NA	-	NA	SHOWER ROD & CURTAINS
12	(-) (-) (-) (-) (-) (-)	3/6 x 6/8	VAULT DOOR	PTD. STEEL	-	NA	DOOR W/ DAMGATE
13	(15) (16) (-) A1.20 A1.20 (-)	3/6 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	1 HR. MIN. RATED ASSEMBLY, 4"x24" VISION LITE GLAZING SHALL BE CLEAR
14	(15) (16) (-) A1.20 A1.20 (-)	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	
15	(15) (16) (-) A1.20 A1.20 (-)	3/0 x 7/0	PTD. STEEL INSUL.	PTD. STEEL	-	40	
16	(15) (16) (-) A1.20 A1.20 (-)	3/0 x 7/0	PTD. STEEL INSUL.	PTD. STEEL	-	40	
17	(15) (16) (-) A1.20 A1.20 (-)	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	1 HR. MIN. RATED ASSEMBLY, 4"x24" VISION LITE GLAZING SHALL BE CLEAR
18	(15) (16) (-) A1.20 A1.20 (-)	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	4"x24" VISION LITE, GLAZING SHALL BE CLEAR
19	(-) (-) (-) (-) (-) (-)	3/0 x 7/4	OMU CASED OPENING	NA	-	NA	SHOWER ROD & CURTAINS
20	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	42	4"x24" VISION LITE, GLAZING SHALL BE CLEAR
21	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	4"x24" VISION LITE, GLAZING SHALL BE CLEAR
22	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	
23	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	42	
24	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	
25	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	
26	(18) (19) (-) A1.21 A1.21 (-)	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	

WINDOW SCHEDULE

MARK	DETAILS	SIZE	DOOR / WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
A	(20) (21) (22) A1.22 A1.22 A1.22	3/4 x 4/0	FIXED	ALUMINUM	TINTED INSULATED, LOW-E	NONE	BLINDS, SEE NOTE 1
B	(20) (21) (22) A1.22 A1.22 A1.22	4/0 x 3/6	FIXED	ALUMINUM	TINTED INSULATED, LOW-E	NONE	BLINDS, SEE NOTE 1
C	(23) (24) (25) A1.22 A1.22 A1.22	12/0 x 6/2	FIXED	ALUMINUM	TINTED INSULATED, LOW-E		
D	(20) (21) (22) A1.22 A1.22 A1.22	3/4 x 4/0	FIXED	HOLLOW METAL	INSULATED, LOW-E		RATED, 3/4 HOUR BLINDS, SEE NOTE 1

FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	WALLS (C3010 NOTE 3)	STC REQD./PRVD.	EXTEND WALL TO DECK ABOVE	FLOOR C3020	WALL BASE (C30208 NOTE 1)	CEILING (C3030 NOTE 3)	CLG. HT.	CABINETRY	NOTES	SO. FT. REQD./PRVD.	COMMENTS
FIRST FLOOR												
100	CANOPY ENTRANCE	NA	NA / 48		CONC	MS	12'-0"				NA/44'	6'x9'-4"; PROVIDE RECESSED MATS
101	REAR ENTRY	EXTERIOR	NA / 48		CONC	MS	9'-0"			(NOTE 8)	NA/20'	PROVIDE RECESSED MATS
102	ENTRY	RHW/EP	42 / 48	YES	QVT	GWB	10'-0"			(NOTE 2) (NOTE 5) (NOTE 8)	120 / 114'	PROVIDE RECESSED MATS
103	LOBBY	RHW/EP	NA / 48		QVT	GWB	10'-0"			(NOTE 8)	NA/426'	PROVIDE RECESSED MATS
104	SIDE ENTRY	EXTERIOR	NA / 48		CONC	PS/MPI	12'-6"			(NOTE 8)	NA/45'	
105	PAGES	EP	NA / 48		CONC	PS/MPI	9'-0"			(NOTE 5)	3825 / 4516'	
106	CSS	P	40 / 48		CONC	ACT	9'-0"			(NOTE 5)	120 / 220'	
107	ARMORY	EP	NA / 48		CONC	PS/MPI	11'-0"			(NOTE 5)	1500 / 1484'	
108	SHOWER	PT	40 / 48		PT	GWB	9'-0"				51 / 59'	
109	HEAD	PT	40 / 48		PT	GWB	9'-0"				48 / 45'	
110	JANITOR	EP	NA / 48		CONC	PS	12'-6"			(NOTE 5)	35 / 28'	
111	MALE HEAD	PT	40 / 48		PT	GWB	9'-0"				270 / 204'	
112	MALE SHOWER	PT	40 / 48		PT	GWB	9'-0"				180 / 191'	
113	MAIN ELECTRICAL ROOM	P	42 / 50	YES	CONC	PS	12'-6"			(NOTE 5) (NOTE 6)	120 / 155'	
114	MECHANICAL ROOM	P	50 / 50	YES	CONC	PS	12'-6"			(NOTE 5) (NOTE 6)	120 / 130'	
115	INTERIOR STAIRS	EP	NA / 48		QVT/RT	PS/MPI	12'-6"			(NOTE 5)	400 / 267'	
116	VESTIBULE	EP	NA / 48	YES	QVT	GWB	10'-0"				NA/66'	PROVIDE RECESSED MATS
SECOND FLOOR												
200	CORRIDOR	RHW/EP	NA / 45		QVT	ACT	9'-6"				NA/983'	PROVIDE RECESSED MATS @ ENTRY
201	TELECOM ROOM	P	42 / 45	YES	QVT	GWB	10'-6"				120 / 148'	FURR DOWN AROUND WIND BEAM AS REQ'D
202	RADIO ROOM	P	45 / 45	YES	CPTT-1	GWB	10'-6"				200 / 197'	FURR DOWN AROUND WIND BEAM AS REQ'D
203	MISSION BREWING ROOM(S) FOR 24	P	45 / 45	YES	CPTT-1	ACT	9'-6"				1050 / 1085'	
204	RIVERINE TASK UNIT COMMANDER OFFICE	P	42 / 45	YES	CPTT-1	ACT	9'-6"				360 / 395'	
205	RIVERINE TASK UNIT OFFICE	P	42 / 45	YES	CPTT-1	ACT	9'-6"				660 / 339'	
206	RIVER OPS CONTROL WATCH STATION	P	42 / 45	YES	CPTT-1	ACT	9'-6"			(NOTE 4)	300 / 205'	
207	SQUADRON INTEROPERABILITY TASK UNIT COMMANDER OFFICE	P	45 / 45	YES	CPTT-1	ACT	9'-6"				360 / 389'	
208	SQUADRON INTEROPERABILITY TASK UNIT OFFICE	P	45 / 45	YES	CPTT-1	ACT	9'-6"				480 / 855'	
209	RIVERINE TASK UNIT COMMANDER OFFICE	P	42 / 45	YES	CPTT-1	ACT	9'-6"				360 / 399'	
210	RIVERINE TASK UNIT OFFICE	P	42 / 45	YES	CPTT-1	ACT	9'-6"				660 / 324'	
211	MALE HEAD	PT	40 / 45		PT	GWB	9'-6"				270 / 197'	
212	FEMALE HEAD	PT	40 / 45		PT	GWB	9'-6"				36 / 32'	
213	MECHANICAL/ELECTRICAL ROOM	P	50 / 51	YES	CONC	PS	VARIABLES			(NOTE 7)	120 / 327'	
214	JANITOR	EP	NA / 45		PT	GWB	9'-6"				35 / 31'	
215	INTERIOR STAIRS	EP	NA / 48	YES	QVT/RT	PS/MPI	9'-6"				400 / 267'	
216	COPY AREA	P	NA / 45		CPTT-1	ACT	9'-6"				NA/74'	
217	CHART ROOM	P	NA / 45		CPTT-1	ACT	9'-6"				NA/122'	
BOAT MAINTENANCE / STAGING BUILDING												
BOAT SPACES		EP/MPI	NA		CONC	RB				(NOTE 5)		
MAINTENANCE SPACE		EP/MPI	NA		CONC	PS/MPI				(NOTE 5)		

NOTES:

- PROVIDE RB AT ALL GWB WALLS.
- INCLUDES ENTRANCE FACILITY, TELECOMMUNICATIONS ROOMS AND OTHER SERVER/LAN ROOMS.
- PAINT ALL STRUCTURAL STEEL COLUMNS, BRACING AND OTHER STRUCTURAL MEMBERS UNLESS INDICATED OTHERWISE.
- PROVIDE DESK-HIGH COUNTERTOP ALONG WINDOWS AND BASE CABINETS, WALL CABINETS AND COUNTERTOP AT COFFEE MESS.
- "PAINTED STRUCTURE" INCLUDES ALL VERTICAL AND HORIZONTAL STRUCTURAL MEMBERS OCCURRING WITHIN THIS SPACE.
- ELECTRICAL AND MECHANICAL ROOMS ON FIRST FLOOR SHALL USE MINIKOOL-1200 2" INDUSTRIAL BOARD.
- ELECTRICAL AND MECHANICAL ROOMS ON SECOND FLOOR SHALL USE MINIKOOL TYPICAL SOUND BARRIER ASSEMBLES STC 51.
- PROVIDE PEREC MAT - ALUMINUM HINGE RECESSED MAT. FRAME 551: ALUMINUM, RECESSED. FRAME 548 MAY BE SUBSTITUTED.
- EXPANDED CONDUIT, JB, DUCTWORK, ETC. IN EXPOSED PAINTED STRUCTURE AREAS SHALL BE ALSO PAINTED.
- MAINTAIN REQUIRED ROOM STC RATING ABOVE CEILING BY EXTENDING STC CONSTRUCTION TO ROOF DECK, OR BY PROVIDING STC RATING AT CEILING.

FINISH LEGEND

ACT	ACOUSTICAL CEILING TILE
CONC	SEALED CONCRETE
CPTT-1	CARPET TILE TYPE 1
CPTT-2	CARPET TILE TYPE 2
EP	EPOXY PAINT
GWB	GYPSUM WALL BOARD
HRWT	IMPACT RESISTANT WALL TREATMENT
MPI	MASTER PAINTERS' INSTITUTE (MPI)
MS	METAL SOFFIT
P	PAINT
PS	PAINTED STRUCTURE
PT	PORCELAIN TILE
QVT	QUARTZ VINYL TILE
RB	RUBBER BASE
RT	RUBBER STAR TREADS



<p>DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI</p> <p>JOHN C. STENNIS SPACE CENTER</p> <p>SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY - PRE-FINAL</p> <p>DOOR, WINDOW & FINISH SCHEDULES</p>	<p>DESIGNED BY: R. WITSE DRAWN BY: J. HIRSHMAN CHECKED BY: T. LARPER IN CHARGE: P. DAMMON</p>	<p>EMMETT G. DAMMON REGISTERED PROFESSIONAL ENGINEER STATE OF MISSISSIPPI LICENSE NO. 9802</p>	<p>DAMMON ENGINEERING, INC. 1000 W. GEMMA AVE. SUITE 200 SIBOLLA, LA 70452 (985) 649-4832</p>		<p>DATE: 07/01/13</p> <p>15026984</p> <p>15026984</p> <p>37 OF 132</p> <p>A17</p>
---	---	--	---	--	--