Luminaire Schedule						
Symbol	Qty	Label	Arrangement	Lumens	LLF	Description
	22	J	SINGLE	27500	0.650	HPIP-TM-250-MT-4-FT-BK
	10	K	SINGLE	50000	0.650	HPTR-3S-400-MT-BK
	5	L	SINGLE	50000	0.650	HPTR-5F-400-MT-BK
	1	Q	BACK-BACK	50000	0.650	HPTR-5F-400-MT-BK

Calculation Summary						
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
CAMPUS-PARK-REAR DRIVE	Illuminance	Fc	1.93	19.4	0.2	9.65	97.00
REAR CAMPUS	Illuminance	Fc	2.04	8.9	0.1	20.40	89.00
FUTURE PARK-ROADWAY	Illuminance	Fc	1.56	5.4	0.1	15.60	54.00

PLAN NORTH

SITE PLAN - PHOTOMETRICS
SECURITY PERIMETER
SCALE: 1"=40'

AUGUST 28, 2009

DEPARTMENT OF THE NAVY — NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST
IPT SOUTH ATLANTIC — NAVAL AIR STATION JACKSONVILLE
JOHN C. STENNIS SPACE CENTER — MISSISSIPPI

SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY

SITE PLAN - PHOTOMETRICS

CODE ID. NO. N4412 | SIZE D
SCALE: 1"=40'
MAXIMO NO. #####
STA. PROJ. NO. #####
WORK ORDER NO. ######
CONSTR. CONTR. NO. N62467-05-D-0096
NAVFAC DRAWING NO. ######-##-#-####
SHEET XXX OF XXX
PH1.4

DES: K. SCHLAFLY | DRW: K. SCHLAFLY
REVIEWED BY: R. WILTSE
PM/DM: T. ARTRIP
CHIEF ENG/ARCH: P. DAMMON

SEAL
M. KIMBALL SCHLAFLY
REG. No. 27699
REGISTERED PROFESSIONAL ENGINEER IN CIVIL ENGINEERING
STATE OF LOUISIANA

SCHLAFLY ENGINEERING LLC
121 SOUTH GENOIS STREET
NEW ORLEANS LA 70119
PHONE 504-415-3347
FAX 504-482-7943
M. KIMBALL SCHLAFLY, P.E.
LA REG 27699

NAVFAC

SYM	DESCRIPTION	DATE	APPR

DRAWFORM REVISION: 01 JAN 2009