

Z5798 "The Pint™" 0.125 gpf Top Spud Ultra Low Consumption Urinal System

Z5798 Series – "The Pint™"

- Zurn One ultra low consumption urinal system designed for optimal performance between Zurn fixture and Zurn flush valve to save water while exceeding industry performance standards.
- 1/8 gpf [0.5 Lpf]
- Over 85% water savings over standard 1.0 gpf [4.0 Lpf] system
- Pressure compensating internal flow regulator
- Oversized footprint to make retrofit easy
- Vitreous china
- High efficiency washout flushing action
- 3/4" top spud
- 2" I.P.S. outlet flange and rubber gasket with integral trap
- 14" extended rim height for handicap compliance when installed at proper height
- Shipping Weight: 72 lbs.

Engineering Specification

- Z5798.205.00 EcoVantage™ High Efficiency Battery-Powered Sensor Urinal System**
System comes complete with sensor-operated, battery-powered exposed ZEG6003EV high efficiency flushometer valve, control stop assembly, and vitreous china urinal. The system is designed to perform to industry standards with as little as 1/8 gallon per flush. Valve is operated by an infrared convergence-type proximity sensor with smart technology, powered by 4 "AA" batteries. Valve features an internal flow regulator to maintain constant flow rates independent of line pressures. Vitreous china urinal is supplied with 3/4" top spud, 2" outlet connection, and strainer assembly.
- Z5798.206.00 EcoVantage™ High Efficiency Hardwired Sensor Urinal System**
System comes complete with sensor-operated, hardwired exposed ZEG6003EV-HW high efficiency flushometer valve, control stop assembly, and vitreous china urinal. The system is designed to perform to industry standards with as little as 1/8 gallon per flush. Valve is operated by an infrared convergence-type proximity sensor with



Z5798 Series 1/8 gpf "The Pint" EcoVantage™ flush valve urinal system.

smart technology, powered by 6 VDC plug-in or hardwired power converter. Valve features an internal flow regulator to maintain constant flow rates independent of line pressures. Vitreous china urinal is supplied with 3/4" top spud, 2" outlet connection, and strainer assembly.

Suffix Options

- UB** Universal retrofit mounting bracket. Time saving urinal mounting bracket allows the urinal to be mounted to existing carrier studs and outlet piping without the need to make any adjustments behind the wall in most applications.

See Zurn One Systems for suggested packages.

This Space is for Architectural/Engineering Approval