INSULATION AND FENESTRATION REQUIREMENTS BY COMPONENT

CLIMATE ZONE	FENESTRATION U-FACTOR	SKYLIGHT U-FACTOR	GLAZED FENESTRATION SHGC	CEILINGS R-VALUE	WOOD FRAME WALLS R-VALUE	FLOORS R-VALUE	BASEMENT WALLS R-VALUE	CRAWL SPACE WALLS R-VALUE
2	0.75	0.75	0.40	30	13	13	0	0

WINDOW SCHEDULE

(A) WINDOW		TYPE				FRAME				GLASS				LITES					ACCESSORIES						REMARKS	MAX. U-FACTOR
		FIXED	VERTICAL SLIDE	HORIZONAL SLIDE	STORE FRONT	STEEL	ALUMINUM	WOOD		TINTED	PLAIN	TRANSLUCENT	WIREGLASS	SEE ELEVATIONS	3/6	4/4	6/6	8/8	ALARM	SCREEN	SHUTTER	NONE				
A	3/4 x 4/8	●			●		●			●				●								●				.75
B	3/4 x 4/8	●			●		●			●				●								●			20 MIN RATED	.75
C	3/4 x 4/8	●			●		●			●				●								●			RATED, SHATTERPROOF	.75
D	3/0 x 3/6			●			●				●											●			RECEPTIONIST WINDOW	

* 1' X 4' SHELF UNDER WINDOW

DOOR & HARDWARE SCHEDULE

(1) DOOR		TYPE					FRAME				HINGE				LOCK					ACCESSORIES								REMARKS
		SOLID WOOD	HOLLOW METAL	ALUM/GLASS	STOREFRONT	MASONITE	STEEL	ALUMINUM	WOOD	CASED OPENING	DBL SWING	BUTT	BURGLERPRF	SLIDING	PASSAGE	PRIVACY	DEADBOLT	KEYED HANDLE	PUSH PULL	PANIC	THRESHOLD	WEATHERSTRIP	DOOR STOP	ALARM	FULL GLASS	CLOSER	HOLD OPEN	
1	3/0 X 6/8		●				●					●						●			●	●						20 MIN. RATED
2	3/0 X 6/8		●				●					●						●			●	●						20 MIN. RATED, SHATTERPROOF
3	3/0 X 6/8	●							●			●						●								●		
4	3/0 X 6/8	●							●			●																
5	2/6 X 6/8	●							●			●						●										
6	2/6 X 6/8	●							●			●																
7	2/0 X 6/8	●							●			●						●										
8	3/0 X 6/8 PR	●							●			●						●										
9	4/0 X 6/8									●																		
10	3/4 X 6/8									●																		

FINISH SCHEDULE

ROOM	FLOOR						BASE						WALLS							CEILING					CLG HT	REMARKS
	CARPET	VINYL TILE	HARDWOOD FLR.	CERAMIC TILE	CONCRETE		VINYL	WOOD	NONE				CERAMIC TILE	CMU	PAINT	GYPSUM BOARD	CONC. BOARD	WAINSCOT	SUSP. ACC. TILE	GYPSUM BOARD	CONCRETE	EXISTING WOOD	NONE			
BUSINESS OFFICES	●							●							●	●			●						10'-0"	
WAITING ROOMS	●							●							●	●			●						10'-0"	
CORRIDORS		●					●								●	●			●						10'-0"	
RESTROOMS				●			●								●	●				●					10'-0"	
EXAM ROOMS		●					●								●	●			●						10'-0"	
OFFICES	●							●							●	●			●						10'-0"	
RESEARCH CLOSETS		●					●								●	●			●						10'-0"	
STORAGE ROOMS					●				●						●	●							●			
KITCHENS		●					●								●	●				●					10'-0"	
ATTIC AREAS					●				●							●							●			