



STRUCTURAL STEEL PLAN  
SCALE: 1/8"=1'-0"

- NOTES:  
1. PROVIDE COLLUM ENCLISURES AND CEILING FURREDOWNS AS NEEDED TO CONCEAL STEEL FRAMEWORK. COORDINATE WITH ARCHITECTURAL PLANS FOR LOCATION OF COLUMNS AND BEAMS

STEEL FRAMING SCHEDULE

TAG	SIZE	LENGTH	FLANGE	WEB	$I_{xx}$ (in <sup>4</sup> )	REMARKS
EXTERIOR DOORS						
1	W/4x109	25'-6"	7/8"	1/2"	1240	
2	(2x) W/4x176	25'-6"	1-5/16"	13/16"	2140	
3	W/4x109	16"	7/8"	1/2"	1240	
4	W/4x109	16"	7/8"	1/2"	1240	
5	W/4x109	16"	7/8"	1/2"	1240	

NOTES:  
1. ALL STEEL SHALL BE ASTM A36 WITH A MIN. YIELD STRESS OF 36 KSI.

REVISIONS	
#	DESCRIPTION

**LA QUINTA INN & SUITES**  
LOT 14  
CABLEA'S PARKWAY  
GONZALES, LA

JOB No:                      DATE: 09-12-2012

DRAWN BY: BSN            CHECKED BY: BSN

The above drawings and specifications, designs and arrangements represented hereby are and shall remain the property of Dammon Engineering, Inc. and no part thereof shall be copied, reproduced or otherwise used in connection with any work or project other than the specific project for which they have been prepared and designed without written consent of Dammon Engineering, Inc. You shall be deemed to have accepted the above drawings and specifications and shall be held responsible for any errors or omissions. Your use of these drawings and specifications shall constitute constructive evidence of acceptance of these restrictions.

**DAMMON**  
ENGINEERING, INC.  
*Architects & Engineers*

CHIEF ENGINEER: EMMETT DAMMON, P.E.  
CHIEF ARCHITECT: ROBERT WILTSE  
554 OLD SPANISH TRAIL  
SLIDELL, LA 70458

dammonengineering.com  
dammoneng@bellsouth.net  
PHONE: 985-649-5832  
FAX: 985-641-5950

STRUCTURAL  
STEEL PLAN

SHEET No: 01 OF 01

S-1