

Report of Concrete Compression

Client: Textron Marine and Land Systems
 Mr. Daniel Latournerie
 1010 Gause Blvd
 Slidell, LA 70458

Project: SSC Facility Improvements at Textron Tarmac -
 19401 Chef Menteur Highway - New Orleans, LA -
 P.O. 118122

Report Date: 03/01/2017 **Sample No:** 24697 **Project No:** C16-087
Report No: 057

Page 1 of 1

Mix Information:

Supplier: Carlo Ditta

Mix Code/Description: 133

Field Data:

Air Temperature, °F: 63
 Concrete Temperature, °F: 74
 Slump, in: 5 1/2

Ticket No: 24109
 Time Batched: 3:52 am
 Time Sampled: 4:32 am
 Time Unloaded: 4:48 am
 Cubic Yards: 10 cu. yds.
 Total Yards: 210.00 cu. yd.
 Water Added at Site: 10 gal.


Field Inspector: M. Robinson

Placement Location: Tarmac paving; portions of sections 6, 7, and 9
 Set Location: 15' W, 5' S of the NW corner of the slab (section 6)

Strength Test Results:

Specifications: 4,000 psi @ 28 days

Lab Nbr	Age (days)	Date Tested	Diameter (in)	Area (in ²)	Maximum Load (lbs)	Break Type	Cure Loc	Compressive Strength (PSI)	Average Strength (PSI)
24697-1A	7	03/03	4.00	12.566	44,625	Type 4	Lab	3,550	3,550
24697-1B	28	03/24	4.00	12.566			Lab		
24697-1C	28	03/24	4.00	12.566			Lab		
24697-1D	HOLD								



Test Method: Unless noted, concrete was sampled and tested in accordance with ASTM C172, C143, C231 or C173, C1064 and C138. Compressive strength tests per ASTM C39.

Remarks: Mix contains super P.

Cylinders Made by Stratum Engr Rep. Cylinders Made by Contractor's Rep. Cylinders Picked up by Stratum Engr Rep. Cylinders Delivered to Stratum Engr Lab

1-ec Dammon Engineering Attn: Mr. Chuck Dammon
 1-ec Textron Marine and Land Systems
 Attn: Mr. Dennis Burke
 1-ec Bindewald & Associates, LLC.
 Attn: Mr. Davy Gant
 1-ec Textron Marine and Land Systems
 Attn: Mr. Daniel Latournerie

Respectfully Submitted,
 Stratum Engineering, LLC



Gregory Richards, Senior Project Manager

1-cc Laboratory

THIS REPORT APPLIES ONLY TO THE STANDARDS OR PROCEDURES INDICATED AND TO THE SAMPLE(S) TESTED AND/OR OBSERVED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF APPARENTLY IDENTICAL OR SIMILAR PRODUCTS OR PROCEDURES, NOR DO THEY REPRESENT AN ONGOING QUALITY ASSURANCE PROGRAM UNLESS SO NOTED. THESE REPORTS ARE FOR THE EXCLUSIVE USE OF THE ADDRESSED CLIENT AND ARE NOT TO BE REPRODUCED WITHOUT WRITTEN PERMISSION.

REPORT CREATED BY ElmTree SYSTEM