



TRANSFER SWITCH AND GENERATOR NOTES:

THE GENERATOR CAN PRODUCE 277/480V, 3Ø. THE GENERATOR WILL SUPPLY 480V 3Ø, 3 POLE SERVICE, NO NEUTRAL. GENERATOR WILL BE GROUNDED TO THE FACILITY GROUND PER MANUFACTURES SPECIFICATIONS.

THE AUTOMATIC TRANSFER SWITCH WILL BE CONNECTED AND OPERATED AT 480V 3Ø, 3 POLE WITHOUT A NEUTRAL CONNECTION. THE ATS WILL BE GROUNDED TO THE FACILITY GROUND PER MANUFACTURES SPECIFICATIONS.