



**RCP NOTES**

1. ALL CEILING HEIGHTS INDICATED ON PLANS ARE FROM TOP OF FINISH FLOOR TO UNDERSIDE OF FINISH CEILING UNLESS OTHERWISE NOTED.
2. REFER TO PARTITION TYPES FOR WALL/PARTITION ASSEMBLY AND INFORMATION.
3. SEE SHEET E101 FOR LIGHT FIXTURE TYPES. SEE MECHANICAL DRAWINGS FOR DIFFUSER AND GRILLE TYPES.
4. PROVIDE ADEQUATE CLEARANCES FOR DUCTS AND RELATED APPURTENANT ITEMS NECESSARY TO MAINTAIN THE SPECIFIED CEILING HEIGHT ABOVE THE FINISH FLOOR FOR LIGHT FIXTURES.
5. PROVIDE HANGER AND SAFETY WIRE FOR LIGHT FIXTURES, SPEAKERS, AND AIR SUPPLY/RETURN DIFFUSERS (AS REQUIRED).
6. ALL ELEMENTS SUSPENDED FROM THE DECK THAT OVERHANGS A PEDESTRIAN WAY SHALL BE A MINIMUM OF 80 INCHES ABOVE THE WALKING SURFACE AS MEASURED FROM THE BOTTOM OF THE OBSTRUCTION.

NOTE:  
REPLACE NECESSARY FIXTURES CAUSED BY REMODEL

**LEGEND**

- GYPSUM BOARD W/ SHEETROCK
- HVAC RETURN AIR GRILL
- HVAC SUPPLY AIR DIFFUSER
- EXHAUST FAN
- EXIT LIGHT
- EMERGENCY WALL LIGHT
- LED FLUORESCENT LIGHT FIXTURE
- RECESSED LIGHT
- WALL SCENCE
- MIRROR LIGHT

**17 REFLECTED CEILING PLAN**  
SCALE: 1/4" = 1'-0"

**DAMMON ENGINEERING, INC.**  
LOUISIANA & MISSISSIPPI  
www.dammonengineering.com  
info@dammonengineering.com  
PH: 985.649.8832

Chief Engineer: Brian Misch, PE  
554 Old Spanish Trail  
Slidell, LA 70458

REVISIONS	DATE
#	DESCRIPTION



**LSA CONSULTANTS**  
36634 BOSWORTH ST.  
SUITE 100  
SUPELL, LA 70458

DATE: 02-13-2023  
DRAWN BY: JAG/ML  
CHECKED BY: JMS

SHEET TITLE:  
REFLECTED CEILING PLAN

DRAWING NUMBER:  
**A103**