

**Fleur De Lis Title US 190 Business Slidell**

Lot 11A

442 Frenaux Ave

Slidell, La

Drainage Calculations - Modified Rational Method, LDOTD Hydraulics Manual

**Predevelopment Condition****25 Year Frequency**

Q= CiA			Factor	Area, sf	Total
	Undeveloped Area		0.2	5,334	1066.7
	Gravel Area		0.6	0	0
	Building/paving		0.95	0	0
				5,334	1066.7
	Weighted C Factor		0.20		
L	Hydraulic Length, L	67	feet		
	Slope, in %, S	1.7910			0.01791
C	Runoff Coefficient, C	0.20			
Tc	Time of Concentration	Tc	20.1	minutes	
		5.191269	6.172558	0.890755	
i	intensity from Region 1		6.27		
		D	0.334855		
		a	4.611		
		b	0.346		
		c	-0.798		
A	Area, Acres	0.122			
	Q25 Flow, cfs	C*i*A	0.15	cfs	

**Q25 Predev Flow****0.15 cfs**

# Fleur De Lis Title US 190 Business Slidell

Lot 11A

442 Frenaux Ave

Drainage Calculations - Modified Rational Method, LDOTD Hydraulics Manual  
**Postdevelopment Condition**  
**25 Year Frequency**

Q= CiA			Factor	Area, sf	Total
	Undeveloped Area		0.2	1,217	243.46
	Gravel Area		0.6	3,499	2099.52
	Building/ paving		0.95	617	586.15
				5,334	2929.13
	Weighted C Factor		0.549		
L	Hydraulic Length, L	137	feet		
	Slope, in %, S	1.8248			0.018248
C	Runoff Coefficient, C	0.549			
Tc	Time of Concentration	Tc	8.5	minutes	
		6.869948	1.969443	0.887458	
i	intensity from Region 1		8.19		
		D	0.140865		
		a	4.611		
		b	0.346		
		c	-0.798		
A	Area, Acres	0.122			
	Q25 Flow, cfs	C*i*A	0.55	cfs	

**Q25 Postdev Flow** **0.55 cfs**

**Q25 Allowable Flow- 90% Undeveloped Flow =** **0.14 cfs**

**Fleur De Lis Title US 190 Business Slidell**

Lot 11A

442 Frenaux Ave

**Drainage Calculations - Modified Rational Method, LDOTD Hydraulics Manual  
Storage Requirements for a 25 Year Frequency Storm Event**

$$i = a(D + b)^c$$

$$q = CiA$$

$$\text{Max Storage Volume} = [(D \times q) - (.5 \times Q_{25} \text{ Allowable Flow} \times (D + T_c))]$$

Storm Duration (D)	Time	i	q, cfs	Max. Storage Volume, cf	Max. Storage Volume, ac-ft
10	min	7.86	0.53	241	0.006
20	min	6.28	0.42	389	0.009
30	min	5.27	0.35	478	0.011
60	min	3.64	0.24	597	0.014
75	min	3.18	0.21	615	0.014
100	min	2.64	0.18	615	0.014
125	min	2.27	0.15	592	0.014

**Discharge End Area Calculations :**

$$q = cA(2gh)^{1/2}$$

Allowable Run Off, q	0.14 cfs	
Friction Factor, c	0.62	
Acceleration, g	32.2 ft/ft/sec	
Height above Invert, H ft	0.5 ft	
End Area, Sq ft	0.04 s.f.	5.674504
Square Inches	5.65 s.i.	
Diameter, Inches	2.68 inches	

**Use 2.68" Diameter Orifice Plate in Terminal CB**

