

## Section 2A.2

### U CHANNEL SIGN POST SPLICE

#### 2A.2.1 MUTCD SECTION REFERENCE

Section 2A Posts and Mountings

#### 2A.2.2 U CHANNEL SIGN POST SPLICE

Structural splices for u-channel sign posts shall be a minimum of 24 inches above the ground, a minimum of 24 inches in length and secured with a minimum of 4 bolts.

Figure 2A.2.1 U Channel Sign Post Splice

