



REVISION/Δ INCLUDES NEW CHAIRHOUSE FOOTPRINT AND RELATED WALKER/STAIR LAYOUT. ADDITION OF MOUNTAIN SIGNAGE. SUBSTITUTION OF ORNAMENTAL STEEL FOR PERIMETER CLEAN LINK FENCING SYSTEM. POSITION OF POOL DECK COLOR AND SPECIFICATION OF CHAIRHOUSE FENCH REVISION.

PERIMETER TREATMENT NOTE:
 RETAINING WALL AND/OR SLOPE SHALL OCCUR AROUND THE PERIMETER PROPERTY LINE OF THIS SITE. EXACT TREATMENT WILL BE DETERMINED AT A LATER DATE BY THE LAND OWNER, CLIENT AND CIVIL ENGINEER. ALL DATA IS CURRENTLY SHOWN KEEPING IN MIND THE CONDITION OF THE EXISTING WALL OR OFF SITE SLOPE TO EXISTING GRADE, UNLESS SHOWN OTHERWISE.

6'-3" HT. ORNAMENTAL STEEL PERIMETER FENCE TOP OF FENCE TO REMAIN LEVEL. STEPS AS REQUIRED IN 3" MAXIMUM INCREMENTS TO ACCOMMODATE GRADE CHANGE. REF. D/B.C. IN AREAS WHERE PERIMETER FENCE IS ACTING AS POOL ENCLOSURE FENCE TO MEET ALL STATE AND LOCAL REQUIREMENTS FOR POOL FENCE AND/OR BARRIER (FENCES TO BE 4' ON CENTER MAXIMUM)

POOL CONSTRUCTION LEGEND

- TC XXXXX
- XXXX
- TOP OF WALL GRADE
- TOP OF WALL ELEVATION
- AD XXXXX
- AREA DRAIN (PER CIVIL ENGINEER)
- AREA DRAIN LOCATION BY L ARCHU (ADDITIONAL LOCATION BY L ARCHU)
- DECK DRAIN LOCATION BY L ARCHU
- DECK DRAIN ELEVATION
- PROPOSED CONTOUR
- DIRECTION OF DRAINAGE
- STONE WALL
- SLOPED WALL
- BRUSH FINISH CONCRETE
- SPECIAL PAVING (REFERENCE PLAN)
- WOOD FENCE
- ORNAMENTAL FENCE
- POOL FENCE
- HANDRAIL / RAILING
- POOL LIGHT
- BOLLARD LIGHT
- TREE UPLIGHT
- POOL LIGHT
- SCENCE LIGHT
- FIBER OPTIC LIGHT
- DRAIN LINE
- JUNCTION BOX
- PROPOSED TREE BALL
- POOL DEPTH (FEET AND INCHES)
- POOL DIMENSIONS
- AIR CONDITIONER
- TRANSFORMER
- ELECTRICAL VETTERS
- BARRIER-FREE RAMP
- AND CURB OPENING
- BARRIER-FREE RAMP
- ACCESSIBLE ROUTE
- 1:20 MAX SLOPE
- CURB OPENING
- IRRIGATION SLEEVE

NOTE:

- REFER TO SHEET 1C FOR CONSTRUCTION AND ACCESSIBILITY NOTES.
- REFER TO SHEET 4C FOR POOL SPECIFICATIONS, NOTES AND DETAILS.
- ALL POOLS AND POOL FACILITIES TO MEET ALL STATE OF LOUISIANA CODES AND STANDARDS AS ADOPTED IN THE LOUISIANA ADMINISTRATIVE CODE TITLE 51, PUBLIC HEALTH SANITARY CODE, PART XXIV, SWIMMING POOLS AND NATURAL OR SEMI-NATURAL SWIMMING OR BATHING PLACES.
- CONNECT DECK AREA DRAIN TO STORY SEWER. REFERENCE CIVIL ENGINEER'S PLANS FOR LOCATION OF STORY SEWER DRAIN AND DRAIN LINE TO BE SIZED BY CIVIL ENGINEER.
- A HOSE BIB AND VACUUM BREAKER SHALL BE PROVIDED FOR WASHING DOWN THE ENTIRE POOL DECK AREA.
- SHOWER AND OUTDOOR DRINKING FOUNTAIN REQUIREMENTS FOR POOL FACILITIES TO BE CONTRIBUTED BY THE LOCAL HEALTH DEPARTMENT OR OTHER AUTHORIZED AGENCY.
- POOL TO BE SALT WATER. ENSURE ALL POOL EQUIPMENT AND RELATED ITEMS MEET SALT WATER REQUIREMENTS AND DESIGN SPECIFICATIONS.

NOTES

- HANDICAP ACCESSIBLE GATE WITH KEY CARD, OR COMBINATION LOCK ONLY.
- * INSTALL ON BOTH SIDES OF GATE.
- WHEN GATE SHIELD IS NOT INSTALLED.
- INSTALL ON OUTSIDE OF POOL FENCE.
- WHEN GATE SHIELD IS INSTALLED.
- REFER TO DETAIL ASC.

