

Rainbow Automatic Chlorine/Bromine Feeders

Years of customer use and satisfaction have proven the Rainbow feeders to be the performance leader in pool & spa chemical dispensers.

FEATURES

- No special venting required
- Completely enclosed system
- No escaping gases
- All Rainbow Feeders are NSF Listed



In-Line Feeders

320 Series. For permanent installation in return line of new or existing pools or spas. Installs in return line on pressure side of pump downstream of all equipment. Standard with 2 in. slip PVC fittings and adapters for 1½ in.

Off-Line Feeders

300 Series. Retrofits into existing pools or spas. Operates on pressure side of pump. Uses ¼ in. feeder hoses, control valve and fittings.



Part No.	Model No.	Description	Pack Qty.	Wt.	UPC 788379+
IN-LINE FEEDERS					
R171096	320	Holds 11 large or 98 small Bromine or Trichlor slow dissolving tablets. Treats from 6,500 up to 27,000 gallons bottom feed and from 18,000 up to 70,000 gallons top feed.	6	30 lbs.	004385
R171218	320C	As above with see-through amber body.	6	30 lbs.	004446
R171100	322	Low profile spa feeder. Holds ½ lb. 1 in. tablets.	6	28 lbs. os	004415
OFF-LINE FEEDERS					
R171016	300	Holds 11 large or 98 small tablets. Treats from 12,000 up to 48,000 gallons.	6	26 lbs. os	004217
R171022	300C	As above with see-through amber body.	6	26 lbs. os	004224
R171026	302	Spa feeder. Includes spa chamber. Treats from 500 up to 2,000 gallons. Holds 15 small tablets.	6	28 lbs. os	004231
R171056	300-19	As above with double-capacity 19 in. chamber. Treats from 13,000 up to 52,000 gallons.	1	5 lbs.	004248
R171066	300-29	As above with triple-capacity 29 in. chamber. Treats from 14,000 up to 57,000 gallons.	1	6 lbs.	004262
COMMERCIAL AND HIGH CAPACITY FEEDERS					
R171070	300-29X	Heavy duty ½ in. control valve and tubing optimizes flow and erosion to provide larger amounts of sanitizer. Dispenses 8.5 lbs. of 1 in. Trichlor in 24 hours. Holds 29 large or 237 small tablets. Treats from 80,000 up to 322,000 gallons.	1	8 lbs.	004279
R171215	HC-3315	High capacity for 1 in. hard plumbing installations. Holds 15 lbs. of tablets. Treats up to 20,200 gallons with Bromine and up to 97,600 gallons with Trichlor.	1	9 lbs.	014988
R171230	HC-3330	High capacity for 1 in. hard plumbing installations. Holds 30 lbs. of tablets. Treats up to 40,000 gallons with Bromine and up to 160,000 gallons with Trichlor.	1	12 lbs.	014995
R171240	HC-3340	High capacity for 1 in. hard plumbing installations. Holds 40 lbs. of tablets. Treats up to 61,000 gallons with Bromine and up to 332,000 gallons with Trichlor.	1	14 lbs.	015008



Feeders-Chlorine/Bromine