

Economy Ladder



- Tubing: 1.90" OD
- Stainless Steel: 304 or 316L Marine Grade* (add -MG to part number)
- Treads: LTDF-101 Plastic (Econoline) or LTDF-103 Stainless Steel (Elite)
- Bends: 6" Radius
- Options: Powder-coating and SealedSteel Salt Friendly available
- Recommended anchors: AS-100B (order separately)
- Recommended escutcheon: EP-100F (order separately)

* Minimum requirement for salt pools is 316L Marine Grade

Econoline	Shipping Weight	Elite	Shipping Weight	Description	Shipping		
					Length	Width	Height
VLLS-102E	21 lbs	VLLS-102S	23 lbs	2-step ladder	61"	29"	2"
VLLS-103E	23 lbs	VLLS-103S	25 lbs	3-step ladder	61"	29"	2"
VLLS-104E	24 lbs	VLLS-104S	27 lbs	4-step ladder	66"	29"	2"

Notes:

- For stock powder-coated products, see page 72. For stock SealedSteel Salt Friendly products, see page 73.
- Frames extend 6½" from the pool wall. Frame is secured to the pool deck with two anchor sockets on 20" centers (Elite model) or 19" centers (Econoline model). The lower end of the frame is bent to meet the pool wall and fitted with two white rubber bumpers (WRB-100A)
- For safety steps substitute the letter T at end of part number. For example, VLLS-102T for a two-step safety ladder.

