



3 LEVEL THREE LAYOUT
SCALE: 1/4" = 1'-0"

MARK	SIZE	DOOR TYPE	FRAME	HANDLE	STIC	FINISH	REMARKS
EXTERIOR DOORS							
①	30x70	SOLID WOOD/FLIGHT	WOOD	1	NA	NA	VERIFY STYLE WITH OWNER
②	30x70	FLIGHT GLASS WOOD/FLIGHT	WOOD	1	NA	NA	VERIFY STYLE WITH OWNER
③	20x70	FLIGHT GLASS WOOD/FLIGHT	WOOD	1	NA	NA	VERIFY STYLE WITH OWNER
④	30x70	FLIGHT GLASS WOOD/FLIGHT	WOOD	2	NA	NA	VERIFY STYLE WITH OWNER
INTERIOR DOORS							
⑤	30x70	WOOD	WOOD	3	NA	NA	EXTERIOR DOOR
⑥	PE 30x70	WOOD	WOOD	2	NA	NA	VERIFY STYLE WITH OWNER
⑦	30x70	WOOD	WOOD	2	NA	NA	VERIFY STYLE WITH OWNER
⑧	11'7" 1/4" 8'7" 0"	CASED OPENING	WOOD	-	NA	NA	VERIFY STYLE WITH OWNER
⑨	70x70	CASED OPENING	WOOD	-	NA	NA	VERIFY STYLE WITH OWNER
⑩	60x70	CASED OPENING	WOOD	-	NA	NA	VERIFY STYLE WITH OWNER
⑪	30x70	WOOD	WOOD	3	NA	NA	VERIFY STYLE WITH OWNER
⑫	30x70	CASED OPENING	WOOD	-	NA	NA	VERIFY STYLE WITH OWNER

MARK	SIZE	WINDOW TYPE	FRAME	GLASS	REMARKS
①	30x60	SINGLE HUNG	ALUMINUM	LOW E	SEE EXT ELEVATIONS
②	30x60	SINGLE HUNG	ALUMINUM	LOW E	ELEVATIONS
③	20x60	SINGLE HUNG	ALUMINUM	LOW E	SEE EXT ELEVATIONS
④	20x60	SINGLE HUNG	ALUMINUM	LOW E	ELEVATIONS

ROOM	WALLS	FLOOR	WALL BASE	WAINSCOT	C&G	CEILING	COMMENTS
RESTROOMS	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
BATHROOMS	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
OPEN BEDRM	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	
CL. (CLOSET)	SIP 1/2" DWS	GF	WB	WAGE	GF	GF	

- GENERAL NOTES:**
- VERIFY ALL DIMENSIONS AND CONDITIONS SHOWN ON DRAWINGS AT THE JOB SITE AND SHALL NOTIFY DESIGNER OF ANY DISCREPANCIES, OMISSIONS, AND/OR CONFLICTS BEFORE PROCEEDING WITH THE JOB.
 - CONTRACTOR MUST COMPLY WITH RULES AND REGULATIONS OF AGENCIES HAVING JURISDICTION AND SHALL CONFORM TO ALL CITY, COUNTY, STATE AND FEDERAL CONSTRUCTION SAFETY AND SANITARY CODES AND ORDINANCES AND ALL CITY, COUNTY, STATE AND FEDERAL MANUFACTURERS RECOMMENDATIONS AND INSTRUCTIONS.
 - ALL WORK SHALL BE PERFORMED BY SKILLED AND QUALIFIED WORKMEN IN ACCORDANCE WITH THE BEST PRACTICES OF THE TRADES INVOLVED, AND IN COMPLIANCE WITH BUILDING REGULATIONS AND/OR GOVERNMENTAL LAWS, STATUTES OR ORDINANCES CONCERNING THE USE OF UNION LABOR.
 - CONTRACTOR SHALL AT ALL TIMES KEEP THE PREMISES FREE OF ACCUMULATION OF WASTE MATERIALS OR RUBBISH. FINISHES TO BE SWEEP CLEAN DAILY OF DEBRIS AND WASTE MATERIALS. AT THE COMPLETION OF THE WORK, LEAVE THE JOB SITE FREE OF ALL MATERIALS AND RUBBISH CLEAN.
 - DO NOT SCALE DRAWINGS; DIMENSIONS GOVERN. LARGER SCALE DRAWINGS SHALL GOVERN SMALLER SCALE.
 - PATCH ALL AREAS WHERE FLOOR IS NOT LEVEL OR TRUE FROM THE INSTALLATION OF FLOORING OR CARPETING.
 - CONTRACTORS SHALL BE RESPONSIBLE FOR THE DISTRIBUTION OF DRAWINGS TO ALL TRADES UNDER HIS JURISDICTION.
 - ALL WORK SHALL BE EXECUTED AND INSTALLED PLUMB, LEVEL, SQUARE, TRUE AND IN PROPER ALIGNMENT.
 - ALL MATERIAL SHALL BE NEW, UNLESS AND OF THE HIGHEST QUALITY IN EVERY RESPECT. LISTED MANUFACTURERS RECOMMENDATIONS AND INSTRUCTIONS.
 - THERE SHALL BE NO SUBSTITUTION OF MATERIALS, WHERE A MANUFACTURER IS SPECIFIED, WITHOUT THE WRITTEN APPROVAL OF THE ARCHITECT.
 - ALL WORK AND MATERIALS SHALL BE GUARANTEED AGAINST DEFECTS.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR CUTTING AND PATCHING REQUIRED FOR HIS WORK.
 - TO INSURE PROPER AND ADEQUATE BLOCKING, ALL BLOCKING FOR CABINET WORK WILL BE THE RESPONSIBILITY OF THE CABINET CONTRACTOR.
 - DIMENSIONS ARE TO CENTERLINE, FACE OF STUDS, CENTER OF COLUMNS, OR FACE OF VENEER.
 - USE 6" STUDS, OR 4" SPACED STUDS AT ALL PLUMBING WALLS.
 - WOOD BRACING PROVIDE 4X8X1/2" TREATED PLYWOOD ON ALL GROUND FLOOR INTERIOR CORNER WALLS WITHIN 8' OF CORNERS. NAIL PLYWOOD EDGES WITH 8d NAILS @ 24" O.C. AT PANEL EDGES AND 6" O.C. AT INTERMEDIATE SUPPORTS.
 - EXTERIOR WALLS SHALL BE DOW CORNING 790 SILICONE. INSTALL IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATION WITH APPROXIMATE TO SELECT COLOR. INTERIOR WALLING TO BE DOW CORNING 790 SILICONE WITH STAPLES.
 - PAINT GRADE TO BE SHERWIN WILLIAMS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS.
 - COVER PROTECTION ON STAIRS.
 - ALL EXTERIOR DOORS ARE TO BE WEATHERSTRIPPED.
 - UPON COMPLETION OF WORK, THE CONTRACTOR SHALL WALK THROUGH WITH OWNER AND COMPLETE A PUNCHLIST OF CORRECTIONS, AND UNSATISFACTORY AND/OR INCOMPLETE WORK.

DAMMON
ENGINEERING, INC.
Architects & Engineers

Chief Architect: Kevin J. Kinchen, NCARB
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458

www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832
F: 985.641.5950

REVISIONS		DATE
#	DESCRIPTION	

NEW ESTATE FOR:
BRUCE & LISA CLUM

THREE JENNIFER LANE
SLIDELL, LOUISIANA 70458

JOB No: 2251 DATE: 08-06-15
DRAWN BY: CKD CHECKED BY: CKD

Below drawings and specifications, design and engineering represented thereby and shall retain the property of Dammon Engineering, Inc. and no part thereof shall be copied, reproduced, or used in connection with any work or project other than that specifically authorized by Dammon Engineering, Inc. without the written consent of Dammon Engineering, Inc. Mutual contact with these drawings or specifications shall constitute acceptance of the drawings and specifications by the contractor.

SHEET TITLE:
LEVEL THREE LAYOUT

DRAWING NUMBER:
A103

SHEET No: 02 OF 5