



NOTE:
 PILE SPACING IS BASED ON 5 TON CAPACITY PER PILE,
 USING CLASS 5 PILEDRIVEN 10' BELOW SURFACE.
 SHOULD PILE LOAD TEST NOT SUPPORT THE 5 TON
 CAPACITY, CONTACT DAMMON ENGINEERING.
 TOTAL OF 82 PILES.

PIILING & FLOOR FRAMING PLAN
 ELEV. 9.00'
 SCALE: 3/16" = 1'-0"

NOTES:
 1. ALL FRAMING LUMBER EXPOSED TO ELEMENTS
 SHALL BE TREATED.
 2. DOUBLE UP F.J. UNDER WALLS THAT RUN PARALLEL TO JOIST.

