



FILE NAME: A:\PROJECTS\2024\2178_CHEF MENTEUR PASS\2178 - Bulkhead Piling Plan.dwg PLOT DATE: 05/02/2024 09:58:48 AM


CHEF MENTEUR PASS



B BULKHEAD PILING PLAN
SCALE: 1" = 10'



B TYPICAL BULKHEAD SECTION
SCALE: 3/16" = 1'-0"



C TYPICAL BULKHEAD SECTION
SCALE: 3/16" = 1'-0"

PILING NOTES

1. PILES ARE TO BE CLASS 5 PRESSURE TREATED WITH A 6 INCH TIP AND 6" BUTT.
2. ALL PILES SHALL BE DRIVEN TO REFUSAL.
3. CONTRACTOR SHALL DRIVE TEST PILE.
4. NO FIELD SUPERVISION OR INSPECTION PROVIDED UNDER THIS SEAL UNLESS OTHERWISE NOTED.
5. FILE LAYOUT MAY BE MODIFIED DUE TO ACTUAL DRIVING CONDITIONS. ENGINEER TO BE NOTIFIED ON ANY MODIFICATION.
7. A PILE BLOW COUNT LOG OF ALL PILES IS TO BE SUBMITTED TO THE ENGINEER OF RECORD. FAILURE TO SUBMIT SAID LOG WILL RELEASE THE ENGINEER OF ALL RESPONSIBILITY AFTER 5 DAYS OF INSTALLING.

GENERAL NOTES

1. ALL LUMBER SHALL BE PRESSURE TREATED WITH A RETENTION OF .4 PER C.F.
2. ALL FASTENERS SHALL BE HOT DIPPED GALVANIZED (HDG) PER ASTM A153.
3. ALL CONNECTORS SHALL BE HDG PER ASTM A653, CLASS G185 SHEET WITH 1.05 OZ/SF ZINC COATING.

DAMMON
ENGINEERING, INC.
 LOUISIANA & MISSISSIPPI

www.dammonengineering.com
 info@dammonengineering.com
 Chief Engineer: Brian Mistich, PE
 554 Old Spanish Trail
 Slidell, LA 70458
 PH: 985.649.5832

#	DESCRIPTION	DATE



BOAT HOUSE PLAN
ALBERT CUTITTO
 LOT 16
 21781 CHEF MENTEUR HWY
 NEW ORLEANS, LOUISIANA, 70121
 JOB No: 2024 DATE: 05-02-2024
 DRAWN BY: CKD CHECKED BY: BAY

SHEET TITLE:
 BULKHEAD PLAN

DRAWING NUMBER:
S102
 SHEET No: 4 of 13