

MAINTAIN AIR SPACE PER MANUFACTURER'S RECOMMENDATIONS FOR FREEZER AND COOLER

FREEZER HEIGHT IS 9'-6" A.F.F. VERIFY CEILING HEIGHT TO BE A MINIMUM OF 13'-0" A.F.F. (CLEAR SPACE) TO ACCOMMODATE A TOP MOUNT COMPRESSOR UNIT.

REMOTE UNITS REQUIRE A MINIMUM 10'-0" A.F.F. (CLEAR SPACE)

REMOTE COMPRESSORS WILL BE USED FOR THIS STORE.

PROVIDE STAINLESS STEEL CLOSURE PIECES TO SEAL AIR SPACE BETWEEN WALL AND COOLERS. SEAL WITH CLEAR SEALANT - TYP.

EXISTING 208V PANEL

UNOBSTRUCTED CEILING HEIGHT 15'-0"

BOH CEILING HEIGHT 10'-0"

TOASTER 208V
TOASTER MUST BE LOCATED 8" AWAY FROM FRP

3'-0" DOUBLE ACTION SWING GATE

NEON SIGN (NS-3)

TOASTY POSTER

SPECIALTY WALL COVERING

DINING RM 438 SQ. FT.
DINING RM CEILING 10 FT.

NEON SIGN (NS-2)
"OPEN"

75'-0"

12'-0"

12'-0"

12'-0"

2'-0"

7'-1"

3'-1"

6'-0"

3'-0"

5'-2 1/2"

3'-10 1/2"

7'-1 1/2"

20'-0"

1500 S.F.

#11329 SCHEMATIC