



1 POWER LAYOUT PLAN - THIRD FLOOR  
 A 203  
 SCALE: 1/8" = 1'-0"

<p><b>GENERAL NOTES:</b></p> <ol style="list-style-type: none"> <li>GENERAL CONTRACTOR TO COORDINATE A PRECONSTRUCTION SITE WALK THROUGH MEETING TO FIELD VERIFY ALL DIMENSIONS AND CONDITIONS WITH OWNER AND ELECTRIC SUBCONTRACTOR PRIOR TO COMMENCING ELECTRICAL WORK AND PURCHASE OF FIXTURES.</li> <li>VERIFY POWER REQUIREMENTS OF ALL APPLIANCES WITH SELECTED APPLIANCE MANUFACTURER.</li> <li>RECESSED LIGHTING FIXTURES RECESSED INTO INSULATED CEILINGS MUST BE APPROVED FOR ZERO CLEARANCE INSULATION COVER (IC) BY UNDERWRITER LABORATORIES OR OTHER TESTING/RATING LABORATORIES RECOGNIZED BY THE INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO).</li> <li>EXHAUST FAN TO BE CAPABLE OF PROVIDING 5 FULL VOLUME AIR CHANGES PER HOUR.</li> <li>WIRING DEVICES: "LEVITON" SPEC. GRADE. COLOR: WHITE. NOT ivory. INSTALL AT HEIGHTS REQUIRED BY CURRENT CODE, U.N.O.</li> <li>EXTENT: COMPLETE WIRING INSTALLATION FOR ALL ROOMS, INCLUDING ALL WIRING AND TELEPHONE CODES. ALL WIRING AND MATERIAL SHALL BE IN FULL ACCORDANCE WITH NATIONAL, STATE AND LOCAL ELECTRICAL CODES INCLUDING TITLE 24.</li> <li>OUTLET HEIGHTS INDICATED ON PLAN ARE TO CENTER OF FIXTURE AND HEIGHT ABOVE THE FINISHED FLOOR ELEVATION. VERIFY CODE COMPLIANCE WITH BUILDING INSPECTOR.</li> <li>OUTLETS AT ALL WADSWORTH DESIGN CUTTING STATIONS SHOULD BE GREY WITH BRUSHED ALUMINUM COVER PLATES AT FLOOR BOX LOCATIONS</li> <li>ALL COVER PLATES AT FLOOR BOX LOCATIONS SHALL HAVE STAINLESS STEEL COVER PLATES.</li> </ol>	<p><b>POWER LEGEND:</b></p> <ul style="list-style-type: none"> <li>WJ WALL MOUNTED FLUSH 4-BOX</li> <li>DUPLX DUPLEX CONVENIENCE OUTLET</li> <li>GRF GROUND FAULT INDICATOR (GRF) RECEPTICAL EXTERIOR WALL MOUNTED WATER RESISTANT CONVENIENCE OUTLET. PROVIDE GROUND FAULT INDICATOR (GRF), TYPICAL.</li> <li>WP HALF SWITCHED CONVENIENCE OUTLET</li> <li>FOURPLX FOURPLX CONVENIENCE OUTLET</li> <li>FLOOR MOUNTED DUPLEX CONVENIENCE OUTLET</li> <li>FLOOR MOUNTED FOURPLX CONVENIENCE OUTLET</li> <li>CM (4) CIRCUITS AT EACH STYLING STATION STUBBED THROUGH CONDUIT IN THE FLOOR. INSTALL THROUGH RECEPTICAL IN PRE-INSTALLED JUNCTION BOX IN STYLING STATION</li> <li>RECESSED RECESSED JUNCTION BOX</li> <li>CEILING MOUNTED OUTLET</li> <li>DATA CONNECTION. VERIFY WITH AV CONSULTANT AND COMPUTER, PHONE PROVIDER.</li> </ul>	<p><b>SPECIALTY NOTES:</b></p> <ol style="list-style-type: none"> <li>CEILING RECEPTICAL PROVIDED WITH AV PROJECTOR. CEILING MOUNT PANEL.</li> <li>PROVIDE CABLE AND QUAD RECEPTICAL FOR FLATSCREEN TELEVISION. COORDINATE MOUNTING HEIGHT WITH A.V. CONSULTANT</li> <li>AV RACK FOR EQUIPMENT LOCATED IN CLOSET. COORDINATE EXACT POWER REQUIREMENT AND LOCATION WITH AV CONSULTANT.</li> <li>OWNER PROVIDED WASHER AND DRYER. VERIFY REQUIREMENTS WITH MANUFACTURER OF SELECTED APPLIANCES.</li> <li>VERIFY POWER AND DATA REQUIREMENTS FOR TIME CLOCK. COORDINATE LOCATION WITH OWNER.</li> <li>PROVIDE 4 DUPLEX OUTLETS EACH WITH A RECEPTICAL CIRCUIT FOR 4 MICROWAVES. COORDINATE HEIGHTS WITH SHELVES FOR MICROWAVES. REFERENCE 6/46-2 FOR DETAILS.</li> <li>OWNER PROVIDED COPIER/PRINTER. VERIFY EQUIPMENT WITH OWNER.</li> <li>PROVIDE 2 DUPLEX OUTLETS EACH WITH A DEDICATED CIRCUIT FOR 2 MICROWAVES. COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES.</li> <li>(2) AT 63" AFF AND (2) AT 78" AFF VERIFY WITH WADSWORTH DESIGN.</li> <li>PROVIDE POWER AND NETWORK CONNECTION AND POINT OF ENTRY FOR NETWORK EQUIPMENT WITH OWNER. VERIFY EXACT LOCATION WITH WADSWORTH DESIGN.</li> <li>PROVIDE POWER FOR OWNER PROVIDED REFRIGERATORS AND VENDING MACHINES. VERIFY EQUIPMENT WITH OWNER.</li> <li>POWER FOR EXTERIOR PARK LIT SIGNAGE. REFER TO EXTERIOR ELEVATIONS FOR DETAILS.</li> <li>OWNER PROVIDED WASHER AND DRYER. VERIFY REQUIREMENTS WITH MANUFACTURER OF SELECTED APPLIANCES.</li> <li>OWNER PROVIDED WASHER AND DRYER. VERIFY REQUIREMENTS WITH MANUFACTURER OF SELECTED APPLIANCES.</li> <li>ELECTRIC HAND DRYER. REFER TO SHEET A401 AND A402 FOR DETAILS.</li> <li>WATERMETER. VERIFY WATER SERVICE GRADE. REFER TO SHEET A401 FOR DETAILS.</li> <li>RELOCATE STAIRS. REFER TO WALL DETAIL FOR DETAILS.</li> <li>OWNER PROVIDED WASHER AND DRYER. VERIFY REQUIREMENTS WITH MANUFACTURER OF SELECTED APPLIANCES.</li> <li>WALL MOUNTED TOOL BAY BY WADSWORTH DESIGN.</li> <li>OWNER PROVIDED SIGN, BENCH AND MACHINES. REFER TO SHEET A401 FOR DETAILS.</li> <li>PROVIDE POWER FOR OWNER PROVIDED REFRIGERATOR.</li> </ol>
--	---	--

NOT FOR CONSTRUCTION: 12.14.09

<p><b>BRADFORD J. DUDLEY</b>        346 THIRD STREET        UQUANA BEACH, OCEANVIEW, 80861        T: 949.278.3078 F: 949.278.3078</p>	<p><b>ETA/eta</b>        E:\Project\Graphic Design Files\VM P&amp;B.jpg</p>	<p><b>METAIRIE, LA</b>        3321 HESSNER AVENUE        METAIRIE, LA 70002</p>	<p><b>CLIENT:</b>        WAK AND USA PUEBRO</p>	<p><b>PROFESSIONAL SEAL:</b></p>
<p><b>POWER LAYOUT PLAN THIRD FLOOR</b></p> <p style="font-size: 2em; font-weight: bold; text-align: center;">A 203</p>	<p><b>DATE</b> 12.01.09</p> <p><b>CONCEPT PLAN</b> 12.01.09</p> <p><b>CONSULTANT CORROBORATION</b> 12.14.09</p>	<p><b>PROJECT NO:</b> 0921</p> <p><b>SCALE:</b> 1/8" = 1'</p>	<p><b>SIGNATURE</b> _____</p> <p><b>DATE</b> _____</p>	