

## ROOM FINISH SCHEDULE

|         | NAME | FLOOR        | BASE |              | WALL   |                | CEILING    |              | REMARKS   |      |                  |              |
|---------|------|--------------|------|--------------|--------|----------------|------------|--------------|-----------|------|------------------|--------------|
|         |      |              | VCT  | CERAMIC TILE | CARPET | CONC. W/SEALER | VINYL BASE | CERAMIC TILE |           | NONE | GYP. BD. PAINTED | CERAMIC TILE |
|         |      |              |      |              |        |                |            |              | CLG. HGT. |      |                  |              |
| SUITE A | 101A | RECEPTION    | ●    |              |        |                |            |              |           |      |                  |              |
|         | 102A | OFFICE       |      |              |        |                |            |              |           |      |                  |              |
|         | 103A | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 104A | HALL         | ●    |              |        |                |            |              |           |      |                  |              |
|         | 105A | RESTROOM     |      |              |        |                |            |              |           |      |                  |              |
|         | 106A | KITCHEN      | ●    |              |        |                |            |              |           |      |                  |              |
|         | 107A | MEDIA ROOM   |      |              |        |                |            |              |           |      |                  |              |
|         | 108A | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 109A | UTILITY ROOM | ●    |              |        |                |            |              |           |      |                  |              |
|         |      |              |      |              |        |                |            |              |           |      |                  |              |
| SUITE B | 101B | RECEPTION    | ●    |              |        |                |            |              |           |      |                  |              |
|         | 102B | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 103B | OFFICE       |      |              |        |                |            |              |           |      |                  |              |
|         | 104B | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 105B | HALL         | ●    |              |        |                |            |              |           |      |                  |              |
|         | 106B | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 107B | RESTROOM     |      |              |        |                |            |              |           |      |                  |              |
|         | 108B | OFFICE       |      |              |        |                |            |              |           |      |                  |              |
|         | 109B | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 110B | KITCHEN      | ●    |              |        |                |            |              |           |      |                  |              |
|         | 111B | OFFICE       |      |              |        |                |            |              |           |      |                  |              |
|         | 112B | CLOSET       |      |              |        |                |            |              |           |      |                  |              |
|         | 113B | UTILITY ROOM | ●    |              |        |                |            |              |           |      |                  |              |

## GENERAL NOTES

1. INSULATION AND INSULATION ASSEMBLIES SHALL MEET THE REQUIREMENTS OF SECTION 719.
- A. CONCEALED INSULATION SHALL HAVE A FLAME SPREAD OF 0-25 AND SMOKE DEVELOPED INDEX OF 0-450, EXCEPT IN COMBUSTIBLE (WOOD FRAME) CONSTRUCTION.
- B. FACING SHALL COMPLY WITH IBC 2006.
2. PROVIDE 5'x5' LANDINGS, LEVEL WITH FINISHED FLOOR, OUTSIDE EXTERIOR DOORS ON WEST SIDE OF BUILDING. THRESHOLDS SHALL BE NOT MORE THAN 1/2" IN HEIGHT AND SHALL BE BEVELED IF MORE THAN 1/4".
3. CONTRACTOR TO VERIFY ALL SITE CONDITIONS, BUILDING LOCATIONS, AND DIMENSIONS PRIOR TO CONSTRUCTION.
4. MATERIALS SHALL BE NEW AND U.L. LISTED.
5. NO WORK SHALL BE CONCEALED UNTIL APPROVED BY LOCAL INSPECTORS.
6. CONSTRUCTION SHALL COMPLY WITH ALL PARISH, STATE, AND LOCAL CODES.
7. CONTRACTOR SHALL FURNISH WATER AND POWER FROM EXISTING SOURCES.
8. EXTERIOR CAULKING SHALL BE THICK CAULK.
9. PAINT GRADE TO SHALL BE SHERWIN WILLIAMS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS. COLOR SELECTION BY OWNER.
10. PROVIDE CLEANUP ON A REGULAR BASIS. NO TRASH STORED IN BUILDING.
11. ALL BATT INSULATION SHALL HAVE A CLASS "A" (0-25) FLAME SPREAD IN COMPLIANCE WITH APPLICABLE CODE.
12. USE 6" STUDS, OR 4" STAGGERED STUDS AT ALL PLUMBING WALLS.
13. PROVIDE GALVANIZED METAL PAN WITH DRAIN AT WATER HEATER LOCATION.
14. ALL CORNERS SHALL BE PROPERLY BRACED FOR WIND LOADS. A 48" SHEATHING SHALL BE PROVIDED EVERY 20 FEET OF WALL LENGTH.
15. FLOORING SHALL BE NON-SLIP.
16. INTERIOR LOCKS ON DOORS IN MEANS OF EGRESS SHALL NOT REQUIRE THE USE OF A KEY, SPECIAL KNOWLEDGE, OR SPECIAL DEVICE TO OPEN IN THE DIRECTION OF EGRESS. ALL DOORS SHALL HAVE LEVER TYPE HANDLES.
17. INTERIOR WALLS AND CEILINGS SHALL HAVE A FLAME SPREAD OF 0-200 AND A SMOKE DEVELOPMENT RATING OF 0-450.
18. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF ALL LOCAL, STATE, AND NATIONAL CODES COVERING THE TYPE OF WORK BEING PERFORMED.
19. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "E" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.
20. ALL FIRE WALLS SHALL EXTEND TIGHT TO ROOF DECK AND BE SEALED WITH AN APPROVED FIRE CAULK.
21. ALL ELECTRICAL, MECHANICAL, AND PLUMBING MATERIALS PENETRATING FIRE WALLS SHALL BE FIRE CAULKED. (PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM-E814.)
22. SERVICE COUNTER SHALL HAVE A HCP ACCESSIBLE WRITING SURFACE, MAX. 36" FROM F.F. (ADAAG MANUAL 1998, PG 135)


## DOOR & HARDWARE SCHEDULE

| NO. | SIZE        | TYPE       |            |              | FRAME |              | HINGE |      | LOCK    |         | ACCESS.  |              |           | REMARKS |           |              |           |                |
|-----|-------------|------------|------------|--------------|-------|--------------|-------|------|---------|---------|----------|--------------|-----------|---------|-----------|--------------|-----------|----------------|
|     |             | S. C. WOOD | H. C. WOOD | HOLLOW METAL | WOOD  | HOLLOW METAL | BUTT  | NONE | PASSAGE | PRIVACY | DEADBOLT | KEYED HANDLE | PUSH PULL |         | THRESHOLD | WEATHERSTRIP | DOOR STOP | CLOSER         |
| 1   | 3/0x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 2   | 3/0x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 3   | 3/0x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 4   | 2/8x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 5   | 2/0x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 6   | PR. 2/6x6/8 | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 7   | 2/8x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 8   | 2/8x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | EXISTING       |
| 9   | 3/0x6/8     | ●          |            |              |       |              |       |      |         |         |          |              |           |         |           |              |           | NEW (SEE NOTE) |

NOTE: EXISTING DOOR 2'-6" WIDE. REPLACE WITH NEW 3'-0" WIDE DOOR.

## WINDOW SCHEDULE

| WINDOW<br>(WIDTH x HT.) | TYPE      |                |            | FRAME |                    | GLASS    |           |        |      | LITES         |      | ACCESS. |         |       | REMARKS |      |  |          |
|-------------------------|-----------|----------------|------------|-------|--------------------|----------|-----------|--------|------|---------------|------|---------|---------|-------|---------|------|--|----------|
|                         | CASHEMENT | FIXED ALUMINUM | STOREFRONT | WOOD  | HOLLOW METAL ALUM. | TEMPERED | INSULATED | TINTED | NONE | SEE ELEVATION | NONE | SCREEN  | SHUTTER | ALARM |         | NONE |  |          |
| Ⓐ 3/0x3/4               | ●         |                |            |       |                    |          |           |        |      |               |      |         |         |       |         |      |  | EXISTING |
| Ⓑ PR. 2/10x3/4          | ●         |                |            |       |                    |          |           |        |      |               |      |         |         |       |         |      |  | EXISTING |
| Ⓒ PR. 2/3x5/0           | ●         |                |            |       |                    |          |           |        |      |               |      |         |         |       |         |      |  | EXISTING |
| Ⓓ PR. 3/4x6/2           | ●         |                |            |       |                    |          |           |        |      |               |      |         |         |       |         |      |  | EXISTING |



**DAMMON**  
ENGINEERING, INC.

CHIEF ENGINEER  
EMMETT  
DAMMON, P.E.

CHIEF ARCHITECT  
ROBERT  
WILTSE

1095 FLORIDA AVENUE  
SLIDELL, LA. 70458  
OFFICE: 985-649-5832  
FAX: 985-641-5950

WEBSITE:  
WWW.DAMMONENGINEERING.COM

EMAIL:  
DAMMONENG@BELLSOUTH.NET

ARCHITECTURE

ENGINEERING

STUDIES

PLANNING

INVESTIGATION

EXPERT WITNESS

OFFICE  
RENOVATION  
FOR ST. TAMMANY  
PARISH SCHOOLS  
SLIDELL, LA

SCHEDULES  
& NOTES

REV:

SCALE: AS NOTED

JOB#: 2035

DATE: 07-07-09

SHEET 6

# A-2

OF 9