

DAMMON ENGINEERING, INC.

dammonengineering.com

ARCHITECTS

ENGINEERS

CONSULTING

DESIGN

STUDIES

EXPERT WITNESS

1095 Florida Ave.
Slidell, LA 70458

P.O. Box 2830
Slidell, LA 70459

985-649-5832
FAX 985-641-5950

June 3, 2010

ADDENDUM No. 1

Project: Sixth Ward Elementary,
Rear of Gym and Cafeteria
Roof Repairs
St. Tammany Parish School Board Project No. 0910

From Dammon Engineering, Inc.
1095 Florida Ave.
Slidell, LA 70458

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents. Acknowledge receipt of the Addendum in the space provided in the Bid Form. Failure to do so may subject Bidder to disqualification.

This Addendum consists of 1 page.

1. Sheet A-6, Partial Elevation and Partial Floor Plan: Adjacent to damaged area of brick to be removed and replaced, over double recessed door opening, and further to the right of the opening, repair and repoint all visible cracks in the brick mortar joints. Also, at recessed double door soffit, seal all gaps where soffit meets brick veneer.
2. Specifications, Modified Bitumen Roofing 07550, Description of Work / Products:
Clarification: DensDeck Prime to be nominal 1/2" thick.
3. Sheet A-2: Existing Equipment, (large air handlers), to be supported by curbs spanning three existing bar joists. Verify that size of new curb is adequate for the weight of equipment supported. A pre-made curb may be required. Provide cricket on roof deck at curb to eliminate any ponding of water at curb.
4. It is the intent that new gutter and downspout metal match other new metal trim and existing metal on adjacent buildings, which is a "green" color.
5. Provide twenty (20) additional Paratread Panels, Detail "G", Sheet A-3 for installation by the STBSB at various ductwork support points to be determined.

END OF DOCUMENT