



**GENERAL NOTES**

1. ALL DIMENSIONS OF EXIST CONDITIONS ARE APPROXIMATE AND SHOULD BE VERIFIED IN FIELD.
2. GENERAL ROOF SLOPE: 1/4" PER FOOT UNLESS NOTED OTHERWISE.
3. MTL GUTTERS SHALL HAVE EXPANSION JOINTS SPACED NOT TO EXCEED 50'.
4. PROVIDE CONG SPLASH BLOCKS WHERE EACH DOWNSPOUT TERMINATES AT GRADE OR ROOF BELOW.
5. ALL NEW MTL GUTTERS TO HAVE EXPANSION JOINTS WITH A SPACING NOT TO EXCEED 50'-0". SEE 8/A2 FOR EXP JT ASSEMBLY DETAIL.

**LEGEND**

- NEW MODIFIED BITUMEN ROOF MEMBRANE SYSTEM WITH 2 1/2" POLYISOCYANURATE INSULATION BOARD INFILL
- NEW MODIFIED BITUMEN ROOF MEMBRANE SYSTEM WITH TAPERED POLYISOCYANURATE INSULATION BOARD INFILL
- EXIST MODIFIED BITUMEN ROOF MEMBRANE WITH NEW PARACOAT ROOF COATING

**KEYNOTES**

MK	DESCRIPTION
1	NEW SBS MODIFIED BITUMEN ROOF SYSTEM. SEE LEGEND ABOVE FOR INSULATION SUBSTRATE INFORMATION.
2	NEW PRE-FINISHED MTL GUTTER. SEE SHEET A2 FOR DETAILS AND 1/A2 FOR GUTTER PROFILE.
3	GUTTER EXPANSION JOINT. SEE 8/A2 FOR ASSEMBLY DETAIL.
4	NEW PRE-FINISHED 6"x6" MTL DOWNSPOUT. D/S PROFILE TO MATCH SMACNA MANUAL FIG. 1-32B. SET D/S 1/2" AWAY FROM WALL AND PROVIDE HANGERS (16GA X1") SPACED NOT MORE THAN 10'-0" OC. HANGER CONFIGURATION TO COMPLY WITH SMACNA MANUAL FIG. 1-35A.
5	EXIST MTL CURBS AND CAP FLASHING TO REMAIN. CONTRACTOR TO VERIFY CURB HEIGHT AND COORDINATE WITH INSUL INFILL TO MEET ROOFING MEMBRANE MFR REQUIREMENTS.
6	REPAIR EXIST ROOF DECK DAMAGE. SCOPE OF DAMAGE APPROX 6 SF ±. CONTRACTOR TO VIF SCOPE OF NEEDED REPAIRS AND REPORT TO ARCHITECT.
7	PATCH EXIST 30"x30" ± ROOF DECK OPENING IN ACCORDANCE WITH SPECIFICATIONS.

**DAMMON**  
ENGINEERING, INC.  
*Architects & Engineers*

www.dammonengineering.com  
504 Poydras Street  
PH: 985.649.5832  
dammon@dammoneng.com  
F: 985.641.5950

Chief Architect: Kevin L. Kinchen, NCAAB  
554 Old Spanish Trail  
Slidell, LA 70458

#	DESCRIPTION	DATE

SEAL:



ROOFING - OLD 6TH GRADE WING:  
SLIDELL HIGH SCHOOL

883 PENNSYLVANIA AVENUE ST. TAMMANY SCHOOL BOARD  
SLIDELL, LA 70458 PROJECT # 1921

JOB NO: 2191 DATE: 2-21-2014  
DRAWN BY: KJK CHECKED BY: KJK

SHEET TITLE:  
ROOF PLAN

DRAWING NUMBER:  
**A1**

SHEET No: 4 of 5