

**MEMORANDUM**

**TO:** All Bidders/ IESI/EAI  
**FROM:** Dale L. Steib, P.E. *DL*  
**DATE:** May 5, 2009  
**SUBJECT:** Addendum No. 2  
IESI Covington Pickup Station Construction

**I. QUESTIONS**

1. Plan Sheet A6.1 indicates that the microwave and refrigerator are NIC. The dishwasher is not noted. Will the owner provide the dishwasher as well? If not, please provide the specification of type and size.

The dishwasher will be provided by the owner as well as all other appliances. Hookups for these appliances are to be installed as given in the plans for future hookups.

2. Section 21.0 on the invitation to bid indicates that a bid bond is NOT required. Section 23.0 (Table B) indicates a bid bond is required. Please advise.

A bid bond is not required. Only a payment and performance bond is required. This table B has a typographical error.

3. Please issue a manufacturer and model number for the Awnings.

I will try to track down the model number and the awning manufacturer from architect. If this information is not obtained in time, please pick something that will work or fit the scheme and document this in the qualifications part of the bid.

4. Please provide a specification for the geotextile fabric and the quantity available on site.

The contractor will supply and install the specified grid and fabric as required. IESI has already purchased 9,000 SY of geotextile fabric (Mirafi 180N) and 7,000 SY of geogrid (Synteen F11) which is located onsite. The contractor should figure the additional amount needed for purchase based on the drawings. The contractor is required to furnish the additional required material and installation of both the material on site and the additional material purchased. The contractor may use any other equivalents to these materials with prior approval. A specification has been included with this addendum.

Daniel B. Kais, P.E.  
President

D. Todd Drummond, P.E.  
Vice President

Chris L. Kafkallides, P.E.  
Vice President

Stephen J. Brasuell, P.E.  
Director

Michael N. Dooley, M.B.A., P.E.  
Director

5. Do we do termite treatment at the office/maintenance building? What about the pickup station?

It will not be needed on the transfer station building but depending on how the maintenance building is ultimately constructed it may be wanted.

Please put this cost as an option in your qualifications of the bid.

## II. CLARIFICATIONS AND ADDITIONAL COMMENTS

1. We have attached the revised "issued for bid" sets of drawings for the pickup station/scale foundations and the deflector plate/fabricated steel. We have attached a summary scoping sheet which tells you of the notable changes made to the drawings so that the subcontractors will not have to go through the full sets again to determine the changes made.
2. The revisions to the transfer station drawings will not be made before the bids are due. The contractors should contact Mr. Dennis Parrino of USA Steel to discuss what materials will require erection for the additional door framing and siding. The contractor should use this conversation to determine his price. Please document in the qualifications as to what was discussed for installation. His contact information is provided below.

Cell – (225) 571-4310

Email – [dparrino@usabidg.com](mailto:dparrino@usabidg.com) or [dparrino@cox.net](mailto:dparrino@cox.net)

3. The revised electrical drawings should be completed by the end of the week and will be issued along with a summary scope of revisions. These are being revised to locate the power for the new doors, relocate the light/control switches near the new entry doors and include emergency lighting at these entry doors.
4. The contractor is to include the price for supplying and installing of all components and hookups of a waste water treatment plant at the scale house. It should be of the same type proposed at the office/maintenance building.
5. The contractor shall bid the office/maintenance building as designed for equal bid comparison. Any proposed changes should be bid as an option for consideration.