

MEMORANDUM

TO: All Bidders/ IESI/EAI
FROM: Dale L. Steib, P.E. *DCS*
DATE: May 8, 2009
SUBJECT: Addendum No. 4
IESI Covington Pickup Station Construction

SAFETY/RISK
FACILITY SERVICES
ENVIRONMENTAL
CIVIL
STRUCTURAL
ARCHITECTURAL
MECHANICAL
PIPING
PROCESS
ELECTRICAL
INSTRUMENTATION
STAFFING

I. QUESTION

1. Is a wind load rating needed for the overhead doors? Anything specific to the doors, i.e. special finishes, motor operation that needs to be added to the basic insulated door?

The overhead doors in the transfer station building will be purchased by IESI and delivered to the site where the contractor will unload and install them. Cajun Overhead Door will be the supplying vendor. They will be all electric with controller openers. There will be 6 doors that include 4 – 12'x14' and 2 – 24'x24'. USA Steel should be contacted about the framing for these doors.

The maintenance building doors that need to be supplied by the contractor are to be wind rated at 120 MPH and need to have the same finishes as the building. We are requesting mechanically opened doors with the base bid but would like you to supply a price for an option to include the electric motors and opening controls. The building will be wired to accept this option as part of the base bid.

Daniel B. Kais, P.E.
President

D. Todd Drummond, P.E.
Vice President

Chris L. Kafkallides, P.E.
Vice President

Stephen J. Brasuell, P.E.
Director

Michael N. Dooley, M.B.A., P.E.
Director